

SURVEY & REMONUMENTATION

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

JOB NUMBER: 94030
SHEET NO. : 1-468

APR 28 1995 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 5:55

For corners in

COMMISSION

Patricia A. Moulton
REGISTER OF DEEDS

MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>24W</u>	E-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER **1** PAGE **139**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Tuesday, December 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<p>E-4: East 1/4 Corner of Section 8, T47N-R24W. 1845: A. D. Sullivan's original subdivision survey notes describe the corner monument as a wood post referenced by: 9" Spruce N89E, 11 L 12" Hemlock S45W, 21 L 1965: The East 1/4 Corner of Section 8 indicated on MDOT R.O.W. map, sheet #42. Distance North listed as 2639.88'. 1973: Plat of survey by Robert F. Cambensy RLS No. 19616 indicates the West 1/4 Corner of Section 9. No corner accessories given.</p>	<p>1977: LCRC by William Donnan RLS No. 17618 indicates a found wood post on ground. Reset 1/2" iron pipe from Highway Dept. witness. Referenced by: 3" Poplar S15E, 13.35' 6" Pine N65E, 20.30' 2" Balsam N30W, 15.70' 1979: Certificate of Survey by Gourdie, Fraser, and Associates, William R. Donnan RLS No. 17618, recorded in Liber 001, Pg. 304, indicates the East 1/4 Corner of Section 8 as a found 1/2" iron pipe. (Continued on reverse side).</p>
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found and accepted GCVN iron and cap No. 27464. Distance North is 2631.83' and distance South is 2639.21'.

**RATIFIED BY PEER GROUP
P.A. 315 OF 1990**
Larry J. Benson
DATE Oct 31, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Replaced 5/8" iron and GCVN cap with a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
5 1/2" White Pine S68E 12.78 ft. GCVN NBT
4" White Pine S24W 12.66 ft. GCVN NBT
5" Balsam N35W 15.68 ft. GCVN NBT
3" Balsam N39E 15.61 ft. GCVN NBT
Green steel sign post West 1.0 ft.
Monument is 0.20 ft. above ground. Butt blazes and BT tags were added to existing NBT's.
Bk. 5, Pg. 85

Signed by *Gerald W. Carlson* Date 12-22-94

Surveyor's Michigan License No. 24589



Record No. 468

*R# 644
900
300 Rem*

Part "A" Continued:

1979 Con't: Referenced by:

3" Aspen	S15E,	13.35'
6" Pine	N65E,	20.30'
2" Balsam	N30W,	15.70'

Distance West listed as 5279.59'.

1964: MDOT found a 2" square post referenced by:

5" Poplar	S15E	13.35'
6" Pine	N65E	20.30'
5" Balsam	N30W	15.70'