

JOB NUMBER: 93300
SHEET NO. : 1-363

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 24W	F-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MARQUETTE COUNTY
REGISTERED FOR
1993 DEC 29 AM 10:39
1 PAGE 49
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Wednesday, December 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13: Quarter Corner common to Section 33, T47N-R24W.	Date unknown - Marquette County field book # 551 indicates
1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:	North 1/4 corner of Section 4, T46N-R24W as an old post at fence intersection. This corner is said to be correct and set from BT's. Set correctly from a Hemlock BT the stump of which remains. This corner has to be the corner for the South 1/4 corner of Section 33 set from BT's because the North 1/4 corner of Section 4 was never set in the original survey. (See reverse side)
20" Hemlock N68E, 21 1	
12" Sugar N51W, 60 1	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found the 3/4" iron pipe as recorded in 1980. Replaced the iron pipe with a Marquette County Survey Monument. Peer group ratification 12-13-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced existing marker with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

- 7" Maple N54W 24.02 ft. Carlson NBT
- 19" Maple N28E 5.08 ft. Carlson NBT
- 5" Maple S73E 10.57 ft. Carlson NBT
- 9" Maple S20E 4.48 ft. Carlson NBT

Monument is 0.4 ft. above ground. An old fence runs North from this corner.
Bk. 4, Pg. 67



Signed by Gerald W. Carlson

Date 12-23-93

Surveyor's Michigan License No. _____

Record No. 363

Part "A" Continued:

1980 - G. Carlson found a 3/4" ID iron pipe 6" high 25 ft. East of the centerline of a small valley on an old fence line to the North. The location of this iron checks with the valley call (0.50 chains) West of the corner.

Referenced by:

12" Twin Maple	N25E 4.95 ft.
5" Maple	S76E 10.38 ft.
9" Maple	S24E 4.44 ft.
7" Maple	N58W 24.17 ft.

L4 RC, Pg. 22

Handwritten:
#9000
V. 1.000
A. 1.000