

1993

COMMISSION

JOB NUMBER: 93300

SHEET NO. : 1-364

For corners in

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

	Located In:	Corner Code #
1. Public Land Survey	T 47N R 24W	G-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTERED IN FIELD

1993 DEC 29 AM 10:40

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

LIBER 1 PAGE 60

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Wednesday, December 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G-13: Section Corner common to Sections 33 and 34, T47N-R24W. 1980 - G. Carlson found a 1/2" iron with RLS cap #20711 on Easterly slope. Referenced by:  
 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:  
 24" Y. Birch N16W, 19 1  
 12" Sugar N38E, 35 1  
 6" Maple S30W 9.90 ft.  
 7" Twin Yellow Birch S78E 3.96 ft.  
 4" Maple N03E 8.68 ft.  
 10" Maple N38W 8.19 ft.  
 29.25 ft. East of the NE corner of Section 4, T46N-R24W  
 Distance 1/2 mile West checks within 0.90 ft. of the G. Carlson 1980 survey. L4 RC, Pg. 22

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 1/2" rebar with RLS cap 20711 on ridge in line with a very old fence to the East and approximately 20 ft. West of an old fence North, 28.22 ft. East of another 1/2" iron with RLS cap 20711 marking the corner for Sections 3 & 4, T45N-R24W. Accepted as location of corner. Peer group ratification 12-13-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced existing marker with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:  
 10" Maple N30W 8.24 ft. Carlson NBT  
 7" Maple N06E 24.58 ft.  
 7" Yellow Birch S70E 3.94 ft. Carlson NBT  
 8" Maple S05E 8.36 ft.  
 Monument is 0.4 ft. above ground.  
 Bk. 4, Pg. 63



Signed by Gerald W. Carlson

Date 12-23-93

Surveyor's Michigan License No. 24589