

SURVEY & REMONUMENTATION

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

JOB NUMBER: 94030
SHEET NO. : 1-472
For corners in

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 5:56

COMMISSION

Patricia A. Monley
REGISTER OF DEEDS

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>24W</u>	<u>H-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER **1** PAGE **143**
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Sunday, November 13, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the *current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management* or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-5: North 1/4 Corner of Section 15, T47N-R24W. 1845: A.D.
Sullivan's original subdivision survey notes describe the corner monument as wood post referenced by:
(No size given) Black Ash S60W, 31 L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: No original evidence found. Corner position calculated proportional distance on line between the NW Corner of the NE Corner of Section 15. Distance West is 2640.05' and distance East is 2639.39'. The GLO chainage was 79.73 for the mile and 39.86 for the East 1/2 mile. The Corner falls in an extremely swampy area where GLO river calls were inconclusive.

WITNESSED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Pusone
DATE Nov 7, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by:
11" Black Ash S25W 25.06 ft. (measured to nail)
Steel sign post N04E 17.24 ft. (with BT tag)
Steel sign post N38E 22.55 ft. (with BT tag)
Steel sign post S53E 24.04 ft. (with BT tag)
Steel sign post S39W 24.04 ft. (with BT tag)
Steel sign post Due South 1.05 ft. (with Survey Marker sign)
Monument is in wet area and is 0.5' above ground. Measured to face of sign posts. Bk. 7, Pg. 117

Signed by Gerald W. Carlson Date 12-22-94
Surveyor's Michigan License No. 24589

