

1993

COMMISSION

JOB NUMBER: 93300

SHEET NO. : 1-366

For corners in

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

	Located In:	Corner Code #
<u>MARQUETTE</u> (County)		
1. Public Land Survey	T 47N R 24W	I-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1993 DEC 29 AM 10:40

REGISTER OF DEEDS

1 PAGE 62  
Register of Deeds Stamp & File Number

LIBER

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Thursday, December 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-13: Section Corner common to Sections 34 and 35, T47N-R24W. 1977 - R. Cambensy indicates the section corner on the recorded plat of Green Garden Hills subdivision. No accessories given.

1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:  
13" Sugar N81E, 35 l  
18" Y. Birch N48W, 42 l

1980 - G. Carlson found a 1" square peg 6" below surface 1 ft. East of centerline of County Road 545.  
Referenced by:  
8" Maple S89W 24.7 ft. 6" Cherry N67W 37.06 ft.  
24" Maple S55E 63.02 ft. 14" Maple S27E 75.85 ft.  
L4 RC, Pg. 25.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1993 - Found 1" square drill rod in County Road 545. Also found 5/8 iron 16.37 ft. West marking the corner common to Section 2 & 3, T46N-R24W. Set Marquette County Survey Monument cap on top of found 1" Sq. drill rod in monument box in pavement of County Road 545. Peer group ratification 12-13-93.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1993 - Placed 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner on top of found 1" square drill rod in pavement of County Road 545 referenced by nails in:  
4" Red Pine S89E 29.20 ft.  
15" Maple S30E 75.95 ft. Carlson NBT  
4" White Pine S63W 50.84 ft.  
5" White Pine N80W 47.90 ft.  
Monument is 0.3 ft. below pavement in monument box at approximate centerline of County Road 545.  
Bk. 4, Pg. 16



Signed by Gerald W. Carlson

Date 12-23-93

Surveyor's Michigan License No. 24589