

SURVEY & REMONUMENTATION

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

JOB NUMBER: 94030
SHEET NO. : 1-474
For corners in

APR 28 1995 **LAND CORNER RECORDATION CERTIFICATE**
Commission **Filing Requirement of Act 74, Mich. P.A. 1970**

1994 DEC 28 PM 5:56

Patricia A. Monley
REGISTER OF DEEDS

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>24W</u>	<u>J-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER **1** PAGE **145**
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Tuesday, December 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5										●			
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-5: North 1/4 Corner of Section 14, T47N-R24W. 1845: A.D.
Sullivan's original subdivision survey notes describe the corner monument as a wood post referenced by:
12" S. Pine S23W, 30 L 12" S. Pine N40E, 07 L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found and accepted a 5/8" re-bar 0.8' above grade 12' +/- North of 2-track road next to slope stake and 4 blazed trees with measuring nails and shiners with P.S. No. 17618. Distance West is 2651.08' and distance East is 2651.54'.

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Larry J. Bussone
DATE Oct 31, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Replaced a 5/8" iron with a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
7" Jack Pine N44W 7.84 ft.
9" Jack Pine N19E 8.50 ft.
6" Jack Pine S76E 26.10 ft.
8" Jack Pine S06E 30.99 ft.
Steel sign post North 1.0 ft.
Monument is 0.30 ft. above ground. Measurements taken are to old tacks with shiners #17618. No record of the monument was known at time of survey. Bk. 5, Pg. 89

Signed by Gerald W. Carlson Date 12-22-94
Surveyor's Michigan License No. 24589

