

SURVEY & REMONUMENTATION

JOB NUMBER: 94030

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

SHEET NO. : 1-475

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 28 PM 5:56

Patricia A. Menley
REGISTER OF DEEDS

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>24W</u>	<u>K-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 1 PAGE 146
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on Wednesday, December 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-5: NE Corner of Section 14, T47N-R24W. 1845: A.D.	1981: Land Corner Recordation Certificate filed by
Sullivan's original subdivision survey notes describe the corner monument as a wood post referenced by:	Glen C. Van Neste indicates a found 1" iron pipe (I.D.) referenced by:
15" Y. Pine N56E, 47 L 8" S. Pine S49W, 65 L	6" Norway Pine S05W 14.53' 8" Jack Pine N55W 38.96'
	8" Jack Pine N18E 32.49' 6" Jack Pine S74E 21.72'
	L 4 RC Pg. 76.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found and accepted iron pipe as referenced in Part A above. Distance West is 2651.54 and distance East is 2651.71'.

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Long J. Busome
DATE Oct 31, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Replaced 1" inside diameter pipe with a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

10" Jack Pine S70E 21.74 ft. GCVN NBT
5" Norway Pine S54W 9.50 ft.
9" Jack Pine N59W 38.92 ft. GCVN NBT
10" Jack Pine N14E 32.49 ft. GCVN NBT
Steel sign post West 1.0 ft.

Monument is 0.20 ft. above ground. Nails in existing NBT's were grown over so new nails were used to measure from. All trees are blazed painted and tagged. Bk. 5, Pg.91

Signed by Gerald W. Carlson

Date 12-22-94

Surveyor's Michigan License No. 24589

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 27, 1971
REVISED MAY 1975
24589
REVISED JAN. 1983

