

1993

COUNTY

JOB NUMBER: 93300
SHEET NO. : 1-368

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

	<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey		T <u>47N</u> R <u>24W</u>	<u>K-13</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

RECEIVED FOR RECORD
 1993 DEC 29 AM 10:40
 MARQUETTE COUNTY
 MICHIGAN
 REGISTER OF DEEDS
 LIBER 1 PAGE 64
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on Thursday, December 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13: Section Corner common to Sections 35 and 36, T47N-R24W.1962 - MDOT highway maps indicate a 5/8" iron pin
 1844: William A. Burt's original survey notes
 describe the corner monument as a wood post referenced by:
 22" Hemlock N45E, 51
 20" Sugar N50W, 401

referenced by:
 14" Maple West 24.40 ft.
 4" Cherry S60E 19.78 ft.
 4" Spruce N35E 58.50 ft.
 Distance is to the 1/4 corner East and 1/4 corner North are given respectively 2630.23 East and 2656.34 North.
 This corner is also referenced as being common to Section 1 & 2 T46N-R24W which is incorrect.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found concrete monument with 1/2" iron set by William Donnan from MDOT highway information. Distance West measures 2615.36 and distance East measures 2630.63 ft. Distance North checks with R. Cambensy and MDOT distance. Accepted concrete monument as the corner. Peer group ratification 12-13-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced concrete monument with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet
 Marquette County Survey Monument stamped to identify the corner referenced by nails in:
 6" Spruce N67E 216.70 ft.
 6" Maple S37E 186.71 ft.
 17" Spruce S46W 108.39 ft.
 6" Poplar N67W 143.99 ft.
 Corner is 139 ft. SW of the centerline of US-41 & KUNDE Rd. intersection.
 Bk. 4, Pg. 75



Signed by Gerald W. Carlson Date 12-28-93

Surveyor's Michigan License No. 24589