

**SURVEY &
REMONUMENTATION**

APR 28 1995

JOB NUMBER: 94030

SHEET NO. : 1-476

For corners in

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 28 PM 5:56

Patricia A. Hanley
REGISTER OF DEEDS

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>24W</u>	<u>L-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER **1** PAGE **147**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on Wednesday, December 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-5: North 1/4 Corner of Section 13, T47N-R24W. 1845: A.D. 1991: Certificate of Survey recorded in L 001 pg. 663 by Sullivan's original subdivision survey notes describe the corner monument as a wood post referenced by:
8" Spruce N58W, 18 L 6" Spruce S40E, 19 L

Glen C. Van Neste indicated a South 1/4 corner Section 12 is a found 1 5/8" iron pipe witnesses as recorded:
6" Jack Pine S60W 13.76' 10" Norway Pine N55W 20.25'
10" Jack Pine N48E 23.99' 9" Jack Pine S70E 11.55'
Distance East is 2651.50'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found and accepted iron pipe as referenced in Part A above. Distance West is 2651.71' and distance East is 2651.40'.

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Gerald W. Carlson
DATE Oct 31, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Replaced a 1 1/2" diameter iron pipe with a 2 1/2" diameter aluminum pipe with a 3 1/4" diameter tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
10" Jack Pine S69E 11.62 ft. GCVN NBT
7" Jack Pine S35W 19.35 ft.
13" Red Pine N63W 20.09 ft. GCVN NBT
12" Jack Pine N47E 23.88 ft. GCVN NBT
Steel sign post South 1.0 ft.
Monument is 0.10 ft. above ground. NBT's are blazed painted and have BT tags.
Bk. 5, Pg. 93



Signed by Gerald W. Carlson Date 12-22-94

Surveyor's Michigan License No. 24589