

# SURVEY & REMONUMENTATION

JOB NUMBER: 94030  
SHEET NO. : 1-485

APR 28 1995

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1994 DEC 28 PM 5:56

For corners in

MARQUETTE  
(County)

COMMISSION

Located In:

Corner Code #

- |                                    |   |     |   |     |      |
|------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey              | T | 47N | R | 24W | M-12 |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
| 2. Property Controlling in Section | S |     | T | R   |      |
|                                    | S |     | T | R   |      |
| 3. Miscellaneous Property in Sec.  | S |     | T | R   |      |
|                                    | S |     | T | R   |      |

*Patricia A. Amley*  
REGISTER OF DEEDS

LIBER 1 PAGE 156  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, GERALD W. CARLSON, in a field survey on Tuesday, December 13, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-12: East 1/4 Corner of Section 36. 1884: William 6" R. Maple N47E, 21.75'  
A. Burt's original survey notes describe the corners 9" R. Maple S48E, 6.0'  
monument as a wood post referenced by: 4" Tw. R. Maple S45W, 5.55'  
10" Maple N55E, 24 L 14" Birch N55W, 17 L 8" R. Maple N39W, 11.0'  
1992: LCRC. recorded by Paul Bressette LLS 37270. Found no L. 5 R.C., Pg. 359  
evidence of OBTs. Corner position reestablished mid-point  
and on-line between the NW and SW Corners of Section 31.  
Distance North to Chocoday River fits proportioned distance  
within 0.5'. DNR monument. Referenced by:

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1994: Found and accepted DNR monument as referenced by Paul Bressette, P.S. No. 37270 in Part A above.  
Distance North is 2644.65 and distance South is 2644.55'.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1994 - Found Department of Natural Resources iron pipe with 4" diameter aluminum cap in place referenced by nails in:  
5" Twin Maple S39W 5.82 ft. Bressette NBT  
8" Maple N48W 11.39 ft. Bressette NBT  
7" Maple N40E 22.07 ft. Bressette NBT  
11" Maple S55E 6.50 ft. Bressette NBT  
Steel sign post West 1.0 ft.  
Monument is stamped MCR 1994 on cap (Marquette County Remonumentation).  
Bk. 5, Pg. 117

**RATIFIED BY PEER GROUP  
P.A. 245 OF 1990**

*Paul J. Bressette*  
DATE Oct 31, 1994

Signed by Gerald W. Carlson

Date 12-22-94

Surveyor's Michigan License No. 24589

