

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE Located In: Corner Code #
(County)

1. Public Land Survey T 48NR 30W D-13
T 47NR 30W D-1 ✓
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

RECORDED Dec. 26, 1996
AT 4:30 O'CLOCK P.M.
LIBER OF PAGE
Patricia A. Mantey
REGISTER OF DEEDS

LIBER **1** PAGE **376**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ALAN K. PIERCE, in a field survey on NOVEMBER 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1			●								
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13			●								

A. Description of original monument and accessories and/or subsequent restoration:

Quarter Corner common to Sections 5 & 32, T47/48N - R30W

D-13: 1846; W. A. John & Austin Burt D. S. set a Maple post witnessed by: 10" Sugar Maple N65°E 45L; 12" Yellow Birch N06°E 8L.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13: 1996; ECI found no original or supporting corner evidence. No known record of any subsequent restoration. Found Mead Corporation metal tag "approximate corner location" S12°E 71.2' from search point which lies about 100' North of woods road. Corner position established at single proportionate distance between E-13 and B-13 and on line between E-13 and Witness Corner to the Meander Corner C/D-13 as a careful and faithful reestablishment of the position of the original corner. The following measurements were taken to G.L.O. terrain calls; East "top ridge" ECI 1400' - G.L.O. 1353'; West "intersect lake" ECI 2216' - G.L.O. 2270'. Distance East is 2631.87' and distance West is 2185.46'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Set a 2-3/8" O.D. aluminum pipe capped with a 3-1/4" aluminum tablet Marquette County Survey monument stamped to identify the corner set about 0.8' above grade. Bearing trees are face, nail & butt blazed and painted yellow with B.T. tags attached. Butt blaze is scribed "B.T.". Distances are measured from a duplex nail with an orange washer stamped "ECI-30097" in the side of the tree. Bearings are magnetic.

6" Aspen N72°E 18.42'; 10" Maple S21°E 17.64'; 12" Maple S15°W 9.71'; 5" Aspen N65°W 12.21'
Steel fence post with survey marker sign - North 1.0'

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussme
DATE 11/4/96



Signed by Alan K. Pierce Date 12-19-96
Surveyor's Michigan License No. 30097