

**SURVEY & REMONUMENTATION**

MAY 22 1997

**COMMISSION**

For corners in  
MARQUETTE  
(County)

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T <u>48</u> N R <u>30</u> W	E-13
	T <u>47</u> N R <u>30</u> W	<u>E-1</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED Dec. 26, 1996  
AT 4:20 O'CLOCK P.M.  
LIBER \_\_\_\_\_ OF \_\_\_\_\_ PAGE \_\_\_\_\_  
Patricia A. Montoy  
REGISTER OF DEEDS

LIBER **1** PAGE **377**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, ALAN K. PIERCE, in a field survey on NOVEMBER 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1				●								
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13				●								

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 4,5,32 & 33, T47/48N - R30W

E-13:  
1846; W. A. John & Austin Burt D. S. set a Maple post witnessed by: 18" Yellow Birch N32°E 37L; 12" Yellow Birch N37°W 33L. 1848; John Burt D. S. witnessed the original post with: 7" Spruce S30°W 34L; 7" Fir S46°E 46L. 1951; Per his personal field notes, R.L.S. No. 4348 set a 1-1/4" drill rod 4' long, 18" above grade, with a cedar post "according to the creek" witnessed by: 7" Basswood N55°E 2.1'; 18" White Pine S12°W 22.8'. 1984; L.L.S. No. 30091 recovered 1-1/4" drill rod witnessed by P.K. nails in: 7" Maple N85°E 24.73'; 14" Basswood N60°E 2.37'; 30" White Pine S10°W 22.95'; 4" Maple S42°W 17.32'. Recorded in L.4R.C., Pg. 401. 1984; Corner shown on unrecorded Certificate of Survey by Clark/Minard Land Surveys, Job No. 84-049. A review of this certificate and others by the same firm shows corners on the West side of Lake Michigan lying essentially on a line determined by this drill rod and meander corner G/H-13.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13:  
1996; ECI recovered 1-1/4" drill rod. No original corner evidence recovered. The following measurements were taken to G.L.O. terrain calls; North "5L stream" ECI 392' - G.L.O. 396' (call used to set corner in 1951); East "leave swamp" ECI 223' - G.L.O. 364' (poorly defined margin), "enter swamp" ECI & G.L.O. 1452'; South "top ridge" ECI 259' - G.L.O. 229' (indistinct) "top ridge" ECI 1233' - G.L.O. 1219'; West "top ridge" ECI 1232' - G.L.O. 1287'. Corner position established by acceptance of 1-1/4" drill rod as a careful and faithful reestablishment of the position of the original corner. Distance East is 1576.91' and distance West is 2631.87'.

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990

Larry J. Bussone  
11/4/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996:  
Replaced 1-1/4" drill rod with a 2-3/8" aluminum pipe capped with a 3-1/4" aluminum tablet Marquette County Survey monument stamped to identify the corner set about 0.5' above grade. Bearing trees are face, nail & butt blazed and painted yellow with B.T. tags attached. Butt blaze is scribed "B.T.". Three 1984 trees were utilized with distances measured from a duplex nail with an orange washer stamped "ECI-30097" in the side of the tree. Bearings are magnetic.

24" Basswood N58°E 2.28'; 28" White Pine S15°W 23.23'; 6" Maple S45°W 17.32'; 5" Maple N28°W 10.10' (N.B.T.)  
Steel fence post with survey marker sign - North 1.2'.

Signed by Alan K. Pierce  
Surveyor's Michigan License No. 30097

Date 12-19-96

