

# SURVEY & REMONUMENTATION

MAY 22 1997

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For **COMMISSION**

MARQUETTE  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- |                                    |                   |              |
|------------------------------------|-------------------|--------------|
| 1. Public Land Survey              | T <u>48NR 30W</u> | <u>K-13</u>  |
|                                    | T <u>47NR 30W</u> | <u>K-1</u> ✓ |
|                                    | T _____           | _____        |
|                                    | T _____           | _____        |
| 2. Property Controlling in Section | S _____           | _____        |
|                                    | S _____           | _____        |
| 3. Miscellaneous Property in Sec.  | S _____           | _____        |
|                                    | S _____           | _____        |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

RECORDED Dec. 26, 1996  
AT 4:20 O'CLOCK P.M.  
LIBER 383 OF \_\_\_\_\_ PAGE \_\_\_\_\_  
Patricia A. Mastey  
REGISTER OF DEEDS

LIBER **1** PAGE **383**  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, ALAN K. PIERCE, in a field survey on NOVEMBER, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

### A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 1,2,35, & 36, T47/48N-R30W

K-13: 1846; W.A. John and Austin Burt D.S. set a Yellow Birch post witnessed by: 10" Sugar N24°E 42L; 7" Hemlock N28°W 58L. 1848; John Burt D.S. witnessed the original post with: 22" Yellow Birch S30°W 13L; 16" Spruce S20°E 21L. 1904; Under special instructions from the G.L.O. Commissioner dated March 17, 1904 and prior to starting a "Survey of fifteen (15) islands in Lake Michigamme", Arthur Kidder D.S. found a marked 6" x 6" iron post 3' above grade. No witnesses noted. M.C.R.C. Book No. 656 notes an iron post - Champion Iron Company. 1982; R.L.S. No. 25836 recovered a 6" x 6" iron post 3' above grade witnessed by P.K. nails in: 6" Maple S08°E 34.42'; 6" Maple S81°E 32.20'; 8" Maple N65°E 8.20'; 8" Maple N22°W 16.72'. Recorded in L.4R.C., Pg. 200. 1982; Corner shown on Page 1 of the "Assessor's Plat of Lake Michigamme" by R.L.S. No. 25836. 1983; Corner shown in L.1S.M. Pg. 499 by R.L.S. No. 25836.

### B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13: 1996; ECI recovered marked 6" x 6" iron post 3' above grade. No original evidence recovered. The following measurements were taken to Original G.L.O. (O.G.L.O.) and Kidder Island Survey (K.G.L.O.) terrain calls: North "descend hill" ECI 509' - O.G.L.O. 524'; East "top of granite ridge" ECI 254' - K.L.G.O. 259', "ascend granite ridge" K.G.L.O. 391' (call indistinct), "top of brushy slope" ECI 2239' - K.G.L.O. 2234'; South "top of ridge" ECI 759' - O.G.L.O. 759'; West "gradual descent over NW slope" ECI 1554' - K.G.L.O. 1584'. Corner position established by acceptance of found iron post as a careful and faithful perpetuation of the position of the original corner. Distance East is 2644.76' and distance West is 2646.34'.

### C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: No additional marking made on cast iron post. Bearing trees are face, nail & butt blazed and painted yellow with B.T. tags attached. Butt blaze is scribed "B.T.". All 1982 trees were utilized with distances measured from a duplex nail with an orange washer stamped "ECI-30097" in the side of the tree. Bearings are magnetic.

10" Twin Maple N86°E 8.15'; 8" Triple Maple S60°E 32.24'; 8" Maple S10°E 34.50'; 10" Maple N30°W 16.65'  
Steel fence post with survey marker sign - North 1.0'.

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990

Larry J. Blum  
DATE 11/14/96

Date 12-19-96

Signed by Alan K. Pierce  
Surveyor's Michigan License No. 30097

