

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

MARQUETTE COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD

1999 FEB 12 PM 3:34

*Robert W. Mackay*  
 REGISTER OF DEEDS

Liber **R 2** of **147**  
 Register of Deeds Stamp & File Number

For corners in

<u>MARQUETTE</u> (County)	SECTION	Located in: Ishpeming Township Ely Township	Corner Code #
1. Public Land Survey	T48N R27W T48N R28W T___ R___ T___ R___	A-03 M-03 ✓	
2. Property Controlling in Section	S___ T___ R___ S___ T___ R___		
3. Miscellaneous Property in Sec.	S___ T___ R___ S___ T___ R___		

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, George M. Platz, in a field survey on December 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Section corner common to: Section 6 T.48N., R.27W.  
 Section 7 T.48N., R.27W.  
 Section 1 T.48N., R.28W.  
 Section 12 T.48N., R.28W.

	A	B	C	D	E	F	G	H	I	J	K	L	M		
1															
2	6			5			4			3			2	1	
3															
4	7						8			9			10	11	12
5															
6	18						17			16			15	14	13
7															
8	19						20			21			22	23	24
9															
10	30						29			28			27	26	25
11															
12	31						32			33			34	35	36
13															

**RATIFIED BY PEER GROUP**  
**P.A. 345 OF 1990**  
*Larry J. Busse*  
 DATE 12/14/98

A. Description of original monument and accessories and/or subsequent restoration:  
 1846: Original US Government Survey by Austin Burt - Set wood post witnessed by:  
 S51°E 18 Links; 30" W Pine  
 N62.5°W 25 Links; 10" Spruce  
 1939: Marquette County Road Commission Field Notes. Iron pin with no witnesses given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 1" iron bar. Found possible remains (stump) of original 30" W. Pine B.T. located S50°E at 18 links. An original GLO line call to the Barnhardt Creek measures 1815' (1749'R) northerly from this found point. A thorough search found no other evidence of any other survey monumentation or occupation in the immediate area. A bent angle iron was found 204.4' north. It was not accepted as the corner. The position of the 1" iron bar has been used and accepted by others as evidenced by line markings. Measurements to adjacent section corners as monumented fit within reason. All measurements, obtainable recorded survey information and any other obtained unrecorded survey information made available to Spalding DeDecker Associates is documented in the research dossier. Considering the above information, all known evidence favors the correctness of this point.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Replaced found 1" iron bar with standard Marquette County Remonumentation Monument, being a 2 3/8" diameter x 30" aluminum post with 3 1/4" diameter aluminum cap stamped with appropriate corner identification and "MCR 1998, PLATZ 38121". Made the following new witnesses:

- Az. 36° 15.68'; Set mag nail w/tag No.38121 in 12" Maple
- Az. 112° 20.42'; Set mag nail w/tag No.38121 in 12" Maple with B.T. tag affixed.
- Az. 176° 26.41'; Set mag nail w/tag No.38121 in 8" Birch
- Az. 264° 29.54'; Set mag nail w/tag No.38121 in 16" Maple



Signed by George M. Platz Date 12-30-98

Surveyor's Michigan License No. 38121