



PK 30038  
#1,000,000

Record No. 396

Part "A" Continued:

Corner was witnessed by:

9" Spruce	S16E	12.86 ft.
10" Jack Pine	N90W	66.44 ft.

and lies approximately 20 ft. South abandoned C&NW railroad road bed.

Attempts to attain C & NW R/W maps met with no response. Corner position accepted upon verification of calculated section of dimensions and was replaced with a 4" square by 36" long concrete monument embedded with a 1/2" rebar and capped with an orange plastic cap stamped "ECI-30097". Bent pin was buried along side the new monument.

Referenced by:

Recovered witnesses:

9" Spruce	S16°E	12.86 ft.
10" Jack Pine	N09°W	66.44 ft.

New witnesses:

6" Jack Pine	S86°W	33.95 ft.
9" Jack Pine	S89°W	154.55 ft.

Bearing trees are face, nail, butt blazed and painted with distances being measured from a nail in the side of the tree. Butt blaze is scribed as "BT". L5 R.C., Pg. 136