

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|---------------------------------------|---------------------------------------|---------------|
| <u>Marquette</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | S <u>16</u> T <u>48N</u> R <u>28W</u> | <u>14</u> |
| 2. Property Controlling in Section | S <u>16</u> T <u>48N</u> R <u>28W</u> | <u>13</u> |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims | | |

Register of Deeds Stamp & File
Number

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

I, Stephan J. Szyszkoski, in a field survey on _____, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

13 Sep 11 2007
14 Sep 06 2007

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 (14-Sec. 16) South 1/16 corner between Sections 15 and 16. Not established in the original survey.
 (13-Sec. 16) Southeast 1/16 corner, Section 16. Not established in the original survey.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (14-Sec. 16) Established the corner midway and on the Section line between Quarter corner 1311.51' north and Section corner 1311.51' south.
 (13-Sec. 16) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set a measuring nail with MDNR tag in the side of the following trees:
 6" Sugar N18E 22.2' mrkd "1/16S BT"
 12" Sugar N89E 14.6' do
 11" Sugar S45W 28.4' do
 7" Sugar N57W 15.7' do
 Set sq'd Cedar post adjacent. Bearings are magnetic.
 (13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set a measuring nail with MDNR tag in the side of the following trees:
 3" Spruce N42E 5.0' mrkd "1/16S BT"
 7" Spruce S44E 30.0' do
 5" Spruce S32W 13.3' do
 10" Spruce N53W 9.1' do
 Set sq'd Spruce post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski Date 10/11/07
 Surveyor's Michigan License No. _____

