

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Marquette</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S 18 T 48N R 28W	16
	S 18 T 48N R 28W	13
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

13 Jun 28 2007
 16 Jun 26 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7	●												
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (16-Sec. 18) East 1/16 corner between Sections 18 and 19. Not established in the original survey.
- (13-Sec. 18) Southeast 1/16 corner, Section 18. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (16-Sec. 18) Established the corner midway and on the Section line between Quarter corner 1322.27' West and Section corner 1322.27' East.
- (13-Sec. 18) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| (16) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
12" Sugar N23W 13.15' wrkd "1/16S 8T"
10" Sugar N86E 26.1' do
13" Sugar S28E 20.1' do
6" Sugar S78W 16.4' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag. | (13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
5" Sugar N11E 10.4' wrkd "1/16S 8T"
6" Sugar N43E 13.0' do
6" Sugar S20E 9.5' do
6" Sugar N88W 5.15' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag. |
|--|---|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/14/07

For the Michigan Department of Natural Resources, Office of Land and Facilities