

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Marquette	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T <u>48N</u> R <u>28W</u>	<u>A7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>18</u> T <u>48N</u> R <u>28W</u>	<u>15</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	●												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Jun 28 2007

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(A7) Corner common to Sections 18-19 T48N-R28W and Sections 13-24 T48N-R29W. 1846 - Established by Wm.A.Burt, Deputy Surveyor: Set Fir post. Sugar 12 S17E [no dist. given in notes], Fir 8 N60W [no dist. given in notes]. 1946 - Marquette Co. Rd. Commission notes state " Cross line south of a rock outcrop. Found no B.T.s Oct. 2, 1946".  
 (15-Sec. 18) West 1/16 corner between Sections 18 and 19. Not monumented in the original survey. The original GLO plat for T48N-R28W shows the corner position to be 20.00 chains west of the Quarter corner between 18 and 19, and 20.34' chains east of the Southwest corner of Section 18.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A7) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record, on the Range line between Section corner 5262.46' South and Quarter corner 7893.69' North.  
 (15) Established the corner on the Section line between Section corner 1358.98' west and Quarter corner 1336.27' east, being proportionate to the original record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 8" Maple N10W 10.9'      mrkd "S13 NBT" 12" Oak N77E 4.5'      "S18 NBT" 17" Maple S04E 26.9'      "S19 NBT" 4" Balsam S79W 4.1'      "S24 NBT"	(15) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 13" Sugar N64E 4.3'      mrkd "1/16S BT" 6" dbl Maple N10E 13.9'      do 17" Y.Birch S08E 30.2'      do 5" Maple N66W 10.85'      do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag.
---	---



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 8/14/07

For the Michigan Department of Natural Resources, Office of Land and Facilities