

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Marquette</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>28W</u>	<u>C6</u>
	T <u>48N</u> R <u>28W</u>	<u>C3</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims	C3 Jul 09 2007	
	C6 Jul 02 2007	

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3		●										
4	7	8	9	10	11	12						
5												
6	18	●	17	16	15	14	13					
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C6) Quarter corner common to Sections 17-18. 1849 - Established by Wells Burt, Deputy Surveyor, midway and on line between Section corners 40.00 chains north and south. BTs: Sugar 14 N4W 39 links, Sugar 14 N75E 36 links. 1946 - Notes of Survey at Marquette Co. Rd. Commission state: Iron pipe and Cedar post. Old B.T. Y.Birch 14 - N16E - 19 links is now a broken stub. Inscription is legible. Fir B.T. has disappeared. Set New B.T.s Spruce 10" S81W 17.0' and Maple 8" N61W 13.3' - Oct. 3, 1946.
 (C3) Corner common to Sections 5-6-7-8. 1848 - Established by Wells Burt, Deputy Surveyor: Set cedar post. Spruce 18 S46W 37 links, Spruce 14 N55E 26 links. 1977 - Shown on survey of Brocky Lake parcels by Duane Peterson, RLS. 1999 - Described as "Iron, Rec. in Rec. Corner Book, in Marquette Co." by Larry Bussone on survey for LaFreniere parcel south of Brocky Lake. No witnesses on either survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C6) The original post and accessories were not recovered. Despite several searches, found no evidence of the position of the original corner on the ground, nor of subsequent monumentation. It appears the 1946 notes do not describe the perpetuation of this corner, but rather the Quarter corner between Sections 7 and 18. Reestablished the corner midway and on the Section line between Section corners 2641.63' north and south.
 (C3) Recovered a 1 1/4" ID iron pipe projecting about 1.5 ft. above ground, firmly set with metal location poster on nearby tree and old sq'd cedar post down on ground, adjacent. Many blazes on trees face this position. Found three nearby trees that seemed to have been marked as witnesses in the past. The position appears to have been accepted as marking the corner position for a long time. Accepted the pipe as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:	(C3) Found 1.25" ID I.pipe. Set measuring nails in:
9" Sugar N60E 4.9' mrkd "1/4S NBT"	5" Hemlock N40E 31.1' mrkd "S5 NBT"
12" Sugar S38E 9.4' do	4" Sugar S72E 23.1' "S8 NBT"
5" Y.Birch S75W 6.6' do	5" Y.Birch S23E 21.4' "S8 NBT"
5" Sugar N30W 10.0' do	14" Cedar N83W 45.0' "S6 NBT"
Set sq'd Spruce post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag.	old wits: 18" Sugar S52E 21.9' to fd. PK nail; 11" Maple, old blaze, S8W 15.8' to C/L; 12" Aspen, dead, N14W 14.8' to C/L. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/14/07