

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|------------------------------------|---------------------------|---------------|
| <u>Marquette</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>48N</u> R <u>28W</u> | <u>E5</u> |
| | T <u>48N</u> R <u>28W</u> | <u>B5</u> |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____

5. Private Claims

85 Jul 03 2007
 E5 Jul 02 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E5) Corner of Sections 8-9-16-17. 1981 - remonumented and recorded by Robert E. Schmeling RLS: Placed a 1" iron pipe with brass cap at proper position as determined from the recovered remains of the original GLO bearing trees: Sugar 12 S70E 41 links - found stump hole; Y.Birch 14 N65W 30 links - found living with scribing visible. New witnesses: Hard Maple 11" S76W 34.8', Hard Maple 9" N10E 21.7', Hard Maple 10" S36E 17.8', Hard Maple 13" S24W 12.8'.

(B5) Quarter corner common to Sections 7 and 18. 1848 - Established by Wells Burt, Deputy Surveyor: Set sugar post on the Section line between Section corner 40.00 chains east and Section corner 40.56 chains west. Y.Birch 14 N16E 19 links, Fir 12 S70W 12 links. 1946 - Notes at Marquette Co. Rd. Commission state: Y. Birch stub 14" N16E 19, old BT. Iron pipe and cedar post. New BTs Spruce 10" S81W 17.0', Maple 8" N61W 13.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E5) Recovered the Schmeling monument in good condition and at record bearing from his witnesses, all in good condition. The distances given in the record to his trees have all been transposed and those shown below are correct. Also recovered the original BT Y.Birch at record bearing and distance. It is now a dead and rotting stub approx. 8' tall with face and scribing visible.

(B5) Found a 3/4" ID Iron pipe projecting 1.1' above ground, in good condition, and at record bearing and distance from the Original BT Y.Birch, now a stump rotted to nearly ground level. Also found the 1946 NBTs at record bearing and distance, in good condition, with lower blazes, no scribing. Accepted the pipe as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|---|--|
| (E5) Fd. 1" ID I.pipe with brass Mead Corp. cap. Set measuring nails in: | (B5) Found 3/4" ID I.pipe. Set measuring nails in: |
| 10" Sugar N13E 34.7' old marks | 14" Spruce S83W 17.0' mrkd "1/4S NBT" * |
| 10" Sugar S32E 21.7' do | 12" Maple N53W 13.3' do * |
| 15" Sugar S27W 17.8' do | 14" Hemlock S24W 8.3' do |
| 15" Sugar S82W 12.8' do & scribing | 13" Sugar N61E 15.0' do |
| Squared a 3" Sugar N23W 3.8' to center for a post. Bearings are magnetic. | Treated 4x4 post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag. * denotes 1946 NBT. |
| Distances are to nail with MDNR tag | |

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/14/07