

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Marquette</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T48N R 28W</u>	<u>E6</u>
	<u>T48N R 28W</u>	<u>E7</u>
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Sept. 5, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E6) Quarter corner common to Sections 16 and 17. 1848 - Established by Wells Burt, Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains north and south. Set Y.Birch post. Spruce 6 S25E 30 links, Y.Birch 14 N15W 18 links.

(E7) Corner common to Sections 16-17-20-21. 1848 - Established by Wells Burt, Deputy Surveyor. Set Maple post. Spruce 8 N35W 28 links, W.Pine 12 S25E 55 links. 1982 - Robert Schmeling, RLS, found pipe set from original bearing trees. Set 1"ID pipe with 4" brass Mead Corp. cap. 10" B.Spruce S48E 37.4', 9" B.Cherry S23W 18.2', 8" B.Spruce S87W 16.8', 9" B.Spruce N28W 28.9'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E6) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record, midway and on the Section line between Section corners 2642.64' north and south.

(E7) Found and accepted the 1982 monument, as described and in good condition. A 1.5" dia. x 6" tall iron pin is adjacent. No obvious evidence of the 1982 NBTs. They, or their remains, may be present: A copy of the 1982 record was not in hand at the time this corner was recovered and coordinated.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set a measuring nail with MDNR tag in:
 8" Sugar S36W 10.1' mrkd "1/4S NBT"
 7" Sugar N64W 21.5' do
 7" Sugar N15E 12.7' do
 5" Sugar S88E 17.3' do
 Set sq'd sugar post adjacent. Bearings are magnetic. Distances are to nail with tag in the side of tree.

(E7) Found 1"ID I.pipe with MEAD Corp. cap. Set a measuring nail with MDNR tag in the side of the following trees:
 9" Spruce N26E 10.1 mrkd "S16 NBT"
 6" Maple N38E 13.9' do
 8" Maple S12E 9.7' "S21 NBT"
 3" Balsam S47W 17.0' "S20 NBT"
 Set sq'd cedar post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski Date 10/11/07

Surveyor's Michigan License No. 33986

