

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Marquette</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T48N R 28W</u>	<u>F5</u>
	<u>T48N R 28W</u>	<u>G5</u>
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File
Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on Sept. 4, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(F5) Quarter corner common to Sections 9 and 16. 1848 - Established by Wells Burt, Deputy Surveyor, midway and on the Section line between Section corners 40.20 chains East and West. Set Maple post. Sugar 8 S45W 15 links, Sugar 10 N52E 28 links.

(G5) Corner common to Section 9-10-15-16. 1848 - Established by Wells Burt. Set Hemlock post. W.Pine 12 S50W 23 links, Spruce 12 N50E 25 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(F5) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record, midway and on the Section line between Section corners 2666.26' East and West.

(G5) The original post was not recovered. Remonumented the corner at the position of an old post hole found in a mound of rock. The post hole lies at record bearing and distance from the rotting remains of what are likely the original BT W.Pine and Spruce, found in advanced stages of decay with no markings visible. Top of hill call 0.50 chain south checks with the original record. A Mead Corp. location poster and blazed trees were found adjacent. Distances to adjacent section corners are: 5332.52' West (5306.4 GLO), 5246.04' South (5280.0 GLO), and 15759.54' East (15841.3' GLO), and to 1/4 corner 7903.21' North (7920.0 GLO).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(F5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set a measuring nail with MDNR tag in:
9" Maple in clump N42E 13.5' mrkd "1/4S NBT"
9" double Maple S69E 12.7' do
10" Sugar S86W 16.8' do
10" Maple in clump N49W 41.8' do
Set sq'd spruce post adjacent. Bearings are magnetic. Distances are to nail in side of tree.
(G5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap made firm in a mound of rock. Set a measuring nail in:
5" Maple N49E 11.4' mrkd "S10 NBT"
7" Spruce N71E 15.9' do Fd. Mead poster here.
9" Spruce S50W 21.7' "S16 NBT"
4" Sugar N51W 14.7' "S9 NBT"
Bearings are magnetic. Distances are to nail with MDNR tag in the side of tree.

Signed by Stephan J. Szyszkoski Date 10/11/07



Surveyor's Michigan License No. 33986