

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Marquette</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R 28W	F7
	T48N R 28W	G6
	T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on Sept. 5, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16	●	15		14		13	
7						●							
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
(F7) Quarter corner common to Sections 16 and 21. 1848 - Established by Wells Burt, Deputy Surveyor, midway and on the Section line between Section corners 40.11 chains east and west. Set Maple post.  
B.Ash 6 N32E 20 links, B.Ash 6 S35W 10 links. Found no subsequent record.

(G6) Quarter corner common to Sections 15 and 16. 1848 - Established by Wells Burt, Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains north and south. Set Cedar post.  
Cedar 14 S35W 37 links, Y.Birch 12 N41E 21 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
(F7) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record, midway and on the Section line between Section corners 2647.34' east and west.

(G6) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record, midway and on the Section line between Section corners 2623.02' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
(F7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set a measuring nail with MDNR tag in the side of the following trees:  
8" Y.Birch N39E 29.4' mrkd "1/4S NBT"  
4" B.Ash N87E 17.1' do  
6" Maple S14E 1.0' do  
5" Sugar N74W 6.8' do  
Set sq'd cedar post adjacent. Bearings are magnetic.

(G6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set a measuring nail with MDNR tag in the side of the following trees:  
10" Spruce N23E 10.7' mrkd "1/4S NBT"  
19" Cedar N78E 22.0' do  
4" Sugar South 9.0' do  
16" Maple N63W 8.1' do  
Set sq'd cedar post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski Date 10/11/07



Surveyor's Michigan License No. 33986