

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Marquette</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>28W</u>	<u>G9</u>
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S <u>16</u> T <u>48N</u> R <u>28W</u>	<u>16</u>
	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on Sept. 11, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G9) Corner common to Sections 21-22-27-28. 1848 - Established by Wells Burt, Deputy Surveyor. Set Hemlock post. Y.Birch 12 S30W 40 links, Y.Birch 9 N54E 21 links. Found no subsequent record.

(16-Sec. 16) East 1/16 corner between Sections 16 and 21. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G9) The original post and accessories were not recovered. Found an iron RR rail set vertically, projecting about 3 ft. above the ground with overgrown blazes and a location poster on nearby trees, facing. The position of the rail is N22E 21 feet from the double proportionate position for this corner based on the original record between monumented corners 2 miles north, 1/2 mile east, 3 miles west, and 2 miles south. I accept the rail as the best available evidence of the position of the original corner.

(16-Sec. 16) Established the corner midway and on the Section line between Quarter corner 1323.67' west and Section corner 1323.67' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G9) Found RR rail set vertically. Set a measuring nail with MDNR tag in the side of the following trees:
 6" Maple S83E 12.8' mrkd "S27 NBT" *
 20" Hemlock S45E 10.3' do **
 8" Y.Birch S72W 34.6' "S28 NBT"
 9" Maple N43W 7.6' "S21 NBT" *
 Bearings are magnetic. * denotes tree with old blaze. ** denotes tree with location poster fd.

(16) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set a measuring nail with MDNR tag in the side of the following trees:
 8" Sugar N49E 23.1' mrkd "1/16S BT"
 16" Sugar S49E 28.4' do
 9" Sugar S51W 4.7' do
 11" Sugar N25W 26.5' do
 Set sq'd Sugar post adjacent. Bearings are magnetic.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7						●						
8	19		20		21		22		23		24	
9						●						
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Signed by Stephan J. Szyszkoski Date 10/11/07

Surveyor's Michigan License No. 33986

