

**SURVEY & REMONUMENTATION**

MAY 22 1997

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48NR 30W	<u>D-13</u>
	T 47NR 30W	D-1
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECORDED Dec. 26 1996  
AT 4:20 O'CLOCK P.M.  
LIBER Patricia A. Mantey OF PAGE \_\_\_\_\_  
REGISTER OF DEEDS

LIBER **1** PAGE **37**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, ALAN K. PIERCE, in a field survey on NOVEMBER, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

Quarter Corner common to Sections 5 & 32, T47/48N - R30W  
D-13: 1846; W. A. John & Austin Burt D. S. set a Maple post witnessed by: 10" Sugar Maple N65°E 45L; 12" Yellow Birch N06°E 8L.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13: 1996; ECI found no original or supporting corner evidence. No known record of any subsequent restoration. Found Mead Corporation metal tag "approximate corner location" S12°E 71.2' from search point which lies about 100' North of woods road. Corner position established at single proportionate distance between E-13 and B-13 and on line between E-13 and Witness Corner to the Meander Corner C/D-13 as a careful and faithful reestablishment of the position of the original corner. The following measurements were taken to G.L.O. terrain calls; East "top ridge" ECI 1400' - G.L.O. 1353'; West "intersect lake" ECI 2216' - G.L.O. 2270'. Distance East is 2631.87' and distance West is 2185.46'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Set a 2-3/8" O.D. aluminum pipe capped with a 3-1/4" aluminum tablet Marquette County Survey monument stamped to identify the corner set about 0.8' above grade. Bearing trees are face, nail & butt blazed and painted yellow with B.T. tags attached. Butt blaze is scribed "B.T.". Distances are measured from a duplex nail with an orange washer stamped "ECI-30097" in the side of the tree. Bearings are magnetic.

6" Aspen N72°E 18.42'; 10" Maple S21°E 17.64'; 12" Maple S15°W 9.71'; 5" Aspen N65°W 12.21'  
Steel fence post with survey marker sign - North 1.0'

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990  
Larry A. Bussone  
DATE 11/4/96

Signed by [Signature]  
Surveyor's Michigan License No. 30097

Date 12-19-96

