

SURVEY & REMONUMENTATION

MAY 2 2 1997

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

MARQUETTE

(County)

Located In:

Corner Code #

1. Public Land Survey

T48N R30W

③ E/F-13 (M.C.)

T47N R30W

③ E/F-1 (M.C.)

T R

T R

2. Property Controlling
In Section

S T R

S T R

#3

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, ALAN K. PIERCE, in a field survey on NOVEMBER 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Witness Corner to Meander Corner to Sections 4 and 33, T47/48N -R30W on the West shore of Lake Michigamme.

W.C. M.C. E/F-13:

1846; W. A. John and Austin Burt D. S. marked a 6" Cedar for Meander Corner. No witnesses established.

1984; Corner shown on an unrecorded survey by Clark/Minard Land Surveys, Job No. 84-027, as a capped rebar on the West shore of Lake Michigamme on line between E-13 and M.C. H/G-13. No witnesses noted.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

W.C. M.C. E/F-13:

1996; ECI recovered 1/2" rebar without registration cap on West shore of Lake Michigamme about 22' West of shoreline. No original evidence recovered. The following measurements were taken to G.L.O. terrain calls; West "enter swamp" ECI and G.L.O. 124', "leave swamp" ECI 1352' - G.L.O. 1213' (swamp margin indistinct). Corner position established by acceptance of 1/2" rebar as a careful and faithful re-establishment of the position of the original corner. Distance East is 5355.33' and distance West is 1576.91'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996:

Replaced capped rebar with a 2-3/8" O.D. aluminum pipe capped with a 3-1/4" aluminum tablet Marquette County Survey monument stamped to identify the corner set about 0.6' above grade. Bearing trees are face, nail & butt blazed and painted yellow with B.T. tags attached. Butt blaze is scribed "B.T.". Distances are measured from a duplex nail with an orange washer stamped "ECI-30097" in the side of the tree. Bearings are magnetic.

10" Cedar N53°E 13.40'; 6" Cedar South 12.71'; 12" Spruce S82°W 1.68'; 16" Cedar N22°W 14.88'
Steel fence post with survey marker sign - North 1.3'.

Signed by Alan K. Pierce

Surveyor's Michigan License No. 30097

Date 12-19-96

RECORDED <u>Dec. 26, 1996</u>
AT <u>4:00</u> O'CLOCK <u>P.M.</u>
LIBER <u> </u> OF <u> </u> PAGE <u> </u>
<u>Patricia D. Montey</u> REGISTER OF DEEDS

LIBER **1** PAGE **378**

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Henry J. Busome

DATE 11/4/96

