

1993

COVERED

JOB NUMBER: 93300

SHEET NO. : 1-334

For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1993 DEC 22 PM 4:13
John A. ...

Located In: MARQUETTE (County) Corner Code #

1. Public Land Survey	T 48N R 25W	<u>A-2</u>
	T 48N R 26W	M-2
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Liber 1 R.C. Page 9
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Wednesday, December 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-2: Quarter Corner common to Section 6, T48N-R25W and Section 1, T48N-R26W. 1845: William A. Burt's original survey notes describe the corner monument as a wood post referenced by: 6" Sugar S43E, 15 l ? Hemlock N58W, 25 l	1988 - G. Carlson set a 5/8 x 18" iron with RLS cap proportionately on line between the NW & SW corners of Section 6. 1 1/4" pipe S70W 117.92 not in correct position. Referenced by: 6" Balsam S71E 29.38 ft. 10" White Birch S04W 21.03 ft. 14" Maple N66W 8.95 ft. 6" Maple N07W 13.29 ft. L5 RC, Pg. 153
--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - The recent remonumentation survey discovered an error in calculating this prior position set by G. Carlson in 1988. The position was found to be 0.30 ft. out of position. Correct position was recalculated and a Marquette County Survey Monument was placed in the corrected position. Corrected position proportionately on line between the SW & NW corners of Section 6. Peer group ratification 11-29-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
6" Maple N05W 13.25 ft.
7" Balsam S70E 29.06 ft.
4" Twin Maple S05W 18.89 ft.
16" Maple N34W 9.20 ft.
Monument is 0.10 ft. above ground.
Bk. 3, Pg. 112



Signed by Gerald W. Carlson Date 12-22-93
Surveyor's Michigan License No. 24589