

1993

COMMISSION

JOB NUMBER: 93300
SHEET NO. : 1-335
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Located In: MARQUETTE (County)

Corner Code A-3

1. Public Land Survey	T 48N R 25W	<u>A-3</u>
	T 48N R 26W	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

70
 RECEIVED FOR FILING
 1993 DEC 22 PM 4: 15
 REGISTER OF DEEDS
 Liber I R.C. Page 19
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Wednesday, December 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-3: Section Corner common to Sections 6 and 7, T48N-R25W 1917 - Cleveland Cliffs Iron Company indicated a standard iron corner set at this corner position with coord. N26484.42, E26316.31. No corner accessories were given.
 and Sections 1 and 12, T48N-R26W. 1845: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
 12" Hemlock S56W, 18 1
 15" Aspen N35E, 25 1
 1987 - G. Carlson found a location tag on a tree and a hole in the ground where the iron pipe appeared to be positioned. This checked well with C.C.I. coordinates for the position of the corner. Set 4" diameter concrete monument with 1/2" rerod for the corner. (See reverse side)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found concrete monument with 1/2" iron as recorded by G. Carlson replaced with Marquette County Survey Monument. Peer group ratification 11-29-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - A 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
 8" Poplar N51W 10.89 ft. Carlson NBT
 8" White Birch N36E 10.71 ft. Carlson NBT
 10" Twin White Birch S53E 20.17 ft. Carlson NBT
 8" Poplar S08E 7.57 ft.
 Monument is 0.4 ft. above ground.
 Bk. 3, Pg. 114



Signed by Gerald W. Carlson Date 12-22-93
 Surveyor's Michigan License No. 24589

Record No. 335

Part "A" Continued:

Referenced by:

8" White Birch	N28E	10.92 ft.
10" White Birch	S56E	20.19 ft.
8" Aspen	N47W	10.75 ft.
8" Twin Oak	S83W	40.68 ft.

#5RC pg. 153

Handwritten notes:
#1900
#1900
#1900
#1900