

1993

COMMISSION

JOB NUMBER: 93300
SHEET NO. : 1-336
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1993 DEC 22 PM 4:13
REGISTERED

Located In: MARQUETTE (County)

Corner Code #

1. Public Land Survey	T <u>48N</u> R <u>25W</u>	<u>A-4</u> ✓
	T <u>48N</u> R <u>26W</u>	<u>M-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Liber 1 R.C. Page 10

Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Wednesday, December 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-4: Quarter Corner common to Section 7, T48N-R25W and Section 12, T48N-R26W. 1845: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
14" Sugar S33E, 38 l
7" Y.Birch N80W, 18 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - No G.L.O. evidence of B.T.'s at mid point between the NW & SW corners was found. A G.L.O. line tree was found at 32.63 chains North of the SW corner that fits with the 10' stream call North of the 1/4 corner position. Ridge call to South fits within 16' of these calls. Corner is set at the G.L.O. distance North of the line tree and on line with the projection of the line from the SW corner through the line tree. Peer group ratification 11-29-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
4" Balsam N23W 13.40 ft.
8" Spruce N86E 33.42 ft.
4" Maple S35E 20.79 ft.
5" Maple S12W 10.13 ft.
Monument is 0.80 ft. above ground.
Bk. 3, Pg. 118



Signed by Gerald W. Carlson Date 12-22-93

Surveyor's Michigan License No. 24589