

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JOB NUMBER: 93300
SHEET NO. : 1-337
For corners in

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 25W	<u>A-5</u> ✓
	T 48N R 26W	M-5
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
MARQUETTE COUNTY
MICHIGAN
1993 DEC 22 PM 4:13
Liber 1 R.C. Page 11
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, GERALD W. CARLSON, in a field survey on Wednesday, December 1, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-5: Section Corner common to Sections 7 and 18, T48N-R25W 1917 - C.C.I. survey data indicated a standard iron corner and Sections 12 and 13, T48N-R26W. 1845: William A. Burt's with coordinates N21265.88, E26326.61. No corner original survey notes describe the corner monument as a accessories given.
wood post referenced by:
10" Maple S71W, 9 l
14" Hemlock N85E, 33 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 2" iron pipe with 3 1/4" diameter brass cap stamped to identify the corner. The distance to the NW corner of Section 7 is found to be within 7' of the old Cleveland Cliffs distance. Corner checks with G.L.O. calls to the North. This corner was found to be in the loose condition. Dirt was packed around it and piled with rock halfway up. Corner is now in stable condition. Left the iron pipe and brass cap as found. Peer group ratification 11-29-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Found a 2" iron pipe with 3 1/4" diameter brass cap stamped to identify the corner set in 1917 by Cleveland Cliffs Iron Company referenced by nails in:
7" Maple N88W 21.21 ft.
5" Maple N45E 13.94 ft.
8" Maple S40E 21.72 ft.
24" Maple S10W 13.81 ft.
Corner is 2' above ground in lowland plain W/N-S rock bluff 35' +/- East.
Bk. 3, Pg. 64 Stamped MCR-1993 on the brass cap.
(Marquette County Remonumentation)



Signed by Gerald W. Carlson Date 12-22-93

Surveyor's Michigan License No. 24589