

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JOB NUMBER: 93300
SHEET NO. : 1-339
For corners in

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1993 DEC 22 PM 4: 14
Gerald W. Carlson
REGISTERED PROFESSIONAL SURVEYOR

Located In: MARQUETTE (County) Corner Code A-7

1. Public Land Survey	T 48N	R 25W	<u>A-7</u> ✓
	T 48N	R 26W	<u>M-7</u>
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Liber 1 R.C. Page 13
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Wednesday, December 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-7: Section Corner common to Sections 18 and 19, T48N-R25W and Sections 13 and 24, T48N-R26W. 1845: William A. Burt's original survey notes describe the corner monument as a wood post referenced by:
24" Y.Birch S63E, 14 l
14" Y.Birch N68W, 48 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - No original evidence of B.T.'s was found on corner location. G.L.O. line calls can't substantiate placement. This corner was set on a proportion between the West 1/4 corner of Section 19 of the NW corner of Section 18. Using the proportioned position, the South 1/4 corner of Section 19 has only a 2 minute deflection on the South line of Section 18 to the pro rated corner, G.L.O. calls on the West line of Section 18 to pro rated corner check well, the general bearing of the range line checks well, G.L.O. tie to the Dead River North of the SW corner of Section 18 fits within 7 feet. Peer group ratification 11-29-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
8" Maple S85W 47.45 ft.
4" Cherry N49W 35.38 ft.
6" Cherry N15W 47.21 ft.
7" Balsam S63W 76.70 ft.
Monument is 0.7 ft. above ground.
Cedar Post N35W 1.92 ft. from monument. Corner lands within the cleared portion of the North/South power line right-of-way near the Westerly edge of the clearing.



Signed by Gerald W. Carlson Date 12-22-93

Surveyor's Michigan License No. 24589