

**SURVEY &
REMONUMENTATION**

1993

COUNTY

JOB NUMBER: 93300

SHEET NO. : 1-333

For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

<u>MARQUETTE</u> (County)	Located In:	Corner Code <u>##</u>
1. Public Land Survey	T <u>48N</u> R <u>25W</u>	<u>B-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1993 DEC 22 PM 4:13
Liber 17 R.C. Page 8
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Tuesday, November 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1: North Quarter Corner of Section 6. Not part of 1988 - G. Carlson set a 5/8 x 18" rerod and RLS cap #24589 original survey. 49.36 ft. West of the South 1/4 corner of Section 31, T49N-R25W at proportional distance between the NW and NE corners of Section 6 and on line between the SW and SE corners of Section 31, T49N-R25W referenced by:
10" Red Pine N26E 22.74 ft. 12" Red Pine N88E 44.81 ft.
6" White Pine S34W 33.08 ft. 12" Red Pine N11W 32.35 ft.
L5 RC, Pg. 154.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 5/8 iron with RLS cap #24589. The recent remonumentation survey discovered an error in placement of this corner in 1988. The correct position calculates out to be about 0.90 West of where it currently sits. Set a Marquette County Survey Monument at the correct proportioned position between the NW & NE corners of Section 6, and online between the SE & SW corners of Section 31, T49N-R25W. Peer group ratification 11-29-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
14" Red Pine N05W 32.15 ft.
12" Red Pine N30E 23.10 ft.
13" Red Pine S55E 28.20 ft.
9" White Pine S32W 32.61 ft.
Monument is 0.50 ft. above ground.
Bk. 3, pg. 106



Signed by Gerald W. Carlson Date 12-22-93

Surveyor's Michigan License No. 24589