

1998 DEC 29 PM 3:20

Patricia A. Mackay
REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 48N R 25W _____ B-5
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER, **R 2** PAGE 101
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5	●											
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, GERALD W. CARLSON, in a field survey on _____, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-5: Quarter Corner common to Sections 7 and 18.
1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by:
8" Y. Birch S18E, 12 L 8" Hemlock N55W, 29 L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5: 1998: No original corner evidence found. The corner was set by single proportionate measurement between the NE and NW corner of Section 18. Distance East is 2629.00' and distance West is 2527.40'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5: 1998: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is flush with the ground. Established references:

10" Red Pine N50E, 56.18' 12" Red Pine N35E, 34.41'
14" Red Pine N38W, 36.99' 12" White Pine N59W, 56.76'

Green Steel Sign Post w/ Yellow Survey Marker Sign, North, 2.0'.

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Bk. 13, Pg. 113

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussone
DATE 11/30/98



Signed by Gerald W. Carlson

Date 12-28-98

Surveyor's Michigan License No. 24589