

1933

COMMISSION

JOB NUMBER: 93300

SHEET NO. : 1-332

For corners in

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
1993 DEC 22 PM 4: 13  
Liber 1 R.C. Page 7  
Register of Deeds Stamp & File Number

Located In:	Corner Code #
MARQUETTE (County)	
1. Public Land Survey	T 48N R 25W C-1
	T R
	T R
	T R
2. Property Controlling in Section	S T R
	S T R
3. Miscellaneous Property in Sec.	S T R
	S T R
4. Lot No. _____, Recorded Plat _____	
5. Private Claims _____	

I, GERALD W. CARLSON, in a field survey on Tuesday, November 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1: Section Corner common to Sections 5 and 6.1845: William 1988 - G. Carlson set a 5/8" x 18" iron and cap 49.5 ft.

A. Burt's original survey notes describe the corner monument West of the SE corner of Section 31, T49N-R25W on line as a wood post referenced by:

7" W.Pine S32E, 11 l	between the SW corner of Section 31, and the SE corner of Section 31 referenced by:
4" W.Pine S37W, 09 l	6" Balsam N46E 13.31 ft.
	10" Maple N90E 09.59 ft.
	10" White Birch S65E 11.13 ft.
	15" White Pine N27W 28.11 ft.
	L5 RC, Pg. 155

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 5/8 iron with G. Carlson RLS cap #24589 replaced with a Marquette County Survey Monument. Peer group ratification 11-29-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced 5/8 iron and RLS cap #24589 with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

20" White Pine N25W 28.05 ft. Carlson NBT
5" Balsam N52E 13.27 ft. Carlson NBT
10" Maple S89E 9.64 ft. Carlson NBT
11" White Birch S66E 11.12 ft. Carlson NBT

Monument is 0.9 ft. above ground.  
Bk. 3, pg. 100



Signed by Gerald W. Carlson

Date 12-22-93

Surveyor's Michigan License No. 24589