

1993

COVER

JOB NUMBER: 93300
SHEET NO. : 1-331
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

	Located In:	Corner Code #
<u>MARQUETTE</u> (County)		
1. Public Land Survey	T <u>48N</u> R <u>25W</u>	<u>D-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1993 DEC 22 PM 4:13

REGISTERED

Liber 1 R.C. Page 6
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on Tuesday, December 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1: North Quarter Corner Section 5. Not part of original 1988 - G. Carlson set aa 5/8 x 18" iron and cap equidistant between the NW & the NE corners of Section 5, on line between the SW & SE corners of Section 32, T49N-R25W referenced by:

- 6" Maple N20E 14.24 ft.
- 16" Red Pine S47W 21.95 ft.
- 6" White Birch N67W 20.01 ft.
- 4" Maple N25W 18.26 ft.

L5 RC, Pg. 158

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 5/8 iron with RLS cap #24589 replaced with a Marquette County Survey Monument.
Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced 5/8 iron with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:

- 8" Twin Maple N14E 14.22 ft. Carlson BT
- 5" Balsam S24E 10.67 ft.
- 17" Red Pine S45W 21.90 ft. Carlson BT
- 7" White Birch N69W 20.06 ft. Carlson BT

Monument is 1.10 ft. above ground.
Bk. 3, pg. 90



Signed by Gerald W. Carlson Date 12-22-93

Surveyor's Michigan License No. 24589