

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE (County) Located In: Corner Code # 1. Public Land Survey T 48N R 25W D-3

Patricia A. Monley REGISTER OF DEEDS

LIBER R 2 PAGE 109

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, GERALD W. CARLSON, in a field survey on MAY 21ST, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. A dot is marked at row 3, column D.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: D-3: Quarter Corner common to Sections 5 and 8. 1845: William Ives' original subdivision survey notes describe the corner as being in a small lake. Referred by: Y. Pine N10E, 78 L (On North side of lake).

1988: An LCRC recorded by Gerald W. Carlson P.S. #24589 in L. 5, RC Pg. 158, indicates that he "searched out in lake for evidence of corner; the water was in excess of 4' deep and nothing was recovered as to being set for the corner. The corner position was calculated by using the coordinates of a previous survey by others. A reference monument 5/8" X 18" Iron and L.S. Cap was set on the N. shore on the N-S 1/4 Line, 41.52' N. of the S. 1/4 Corner, and a 5/8" X 18" Iron and Cap was set on the N.-S. 1/4 Line, 20.00' N. of the aforementioned Reference Iron". 5/8" X 18" Reference Monument referenced by: 12" R. Pine N19W, 11.95' 16" R. Pine N55W, 18.01' 12" R. Pine N29E, 11.04' 12" R. Pine S84E, 10.85' Water's Edge of Lake South, 6.8' 5/8" X 18" Iron & Cap North, 20.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: D-3: 1998: No original corner evidence found. Found and accepted a 5/8" Iron. Bearings and distances to 5 found references checked very well (except for the distance to the 12" R. Pine, N19W) with those recorded in L. 5, RC Pg. 158. Distance East is 2638.72' and distance West is 2630.31'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: D-3: 1998: Replaced found 5/8" X 18" Iron Witness Corner with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner as a Witness Corner 41.52' North of the actual 1/4 Corner location. Monument is flush with ground. Measured existing references to fd. d.h. nails and washers: 13" R. Pine N18W, 10.86' (Carlson NBT) 17" R. Pine N51W, 17.71' (to set d.h. nail) (Carlson NBT) 13" R. Pine N34E, 11.01' (Carlson NBT) 13" R. Pine S88E, 10.77' (Carlson NBT) Water's Edge of Lake South, 5.7' 5/8" X 18" Iron & Cap North, 19.85' (Carlson Accessory)

Set Green Steel Sign Post w/ Yellow Survey Marker Sign Due South, 1.48'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Bk. 13, Pg. 111.

RATIFIED BY PEER GROUP P.A. 345 OF 1990 Date 11/30/98



Signed by Gerald W Carlson Date 12-28-98

Surveyor's Michigan License No. 24589