

MAY 22 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1996 DEC -4 AM 10:11

Patricia A. Manley REGISTER OF DEEDS

For corners in MARQUETTE (County)

Located In: Corner Code #

- 1. Public Land Survey T 48N R 25W D-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

LIBER 1 PAGE 332 Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on JUNE 28TH, 19 96, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked at row 9, column C.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: D-9: Quarter Corner common to Sections 20 and 29.

1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by: 8" Cedar N50W, 04 L 12" Cedar S40E, 09 L

1904: Charles Cummings, in Record of Surveys Pg. 151, indicates the corner as being set from a 12" Cedar bearing S40E, 9 L. Distance North to North 1/4 Corner is 5284.0', and distance East to S.E. Corner Section 20 is 2616.0'.

No Date: MCRC F.B. #526, pp. 17 and 18, indicate the corner on fence line located from Cedar (possible B.T.) East of old road. (SEE REVERSE SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: D-9: 1996: Searched and found no evidence of original B.T.'s. Found and accepted a 1 1/4" O.D. iron Pipe capped with a 4" State of Michigan Brass Cap, 1.1' high, and stamped to identify the corner. Corner is located in a small opening among blown down trees in moderately swampy terrain. Checked Line Call: (Leave Swamp at Stream 8 L, coursing North, 6.05 chains [399'] West of corner). Measured call: West, 408', intersected clear, sand bottom stream, 7' wide, coursing Due North. East side of stream is Cedar Swamp. Abrupt change to mature mixed hardwoods as land rises evenly to West of stream. Checked Line Call: (Leave swamp coursing N.N.E., 5.00 chains [330'] East of corner). Measured call: East, 315' (down old grown-in brush line running parallel to, and +/- 5' North of old and down barbed wire fence), hit marked change in vegetation from Cedar and Balsams in swamp to mixed hardwoods near base of low rise to East bearing N20E. Distance East is 2613.13' and West is 2612.60'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9: 1996: Stamped "MCR 1996" on found brass cap. Checked bearings and distances to found references: 18" Cedar N03W, 43.11' (Carlson NBT) 15" W. Birch N55W, 22.25' (Carlson NBT) 9" Box Elder (Prev. called Elm) S27E, 24.16' (Carlson NBT) 20" Spruce (Dead and down) (Carlson NBT)

Established references: 11" Cedar S43W, 32.30' Green Steel Sign Post w/ Yellow Survey Marker Sign N14E, 01.00' (To face)

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed. Added d.h. nail directly above found P.K. nail on 15" W. Birch. Other found witness trees already had face and nail blazes and d.h. nails.

RATIFIED BY PEER GROUP P.A. 345 OF 1990

DATE 11/11/96



Signed by Gerald W. Carlson

Date 12-2-96

Surveyor's Michigan License No. 24589

9:
PART A CONTINUED:

9214
Geo. Sam

o Date: MCRC field notes (No book or page # given) indicate a post on fence line (possible B.T.), and also indicate a 1/2" iron pin.

o Date: MCRC field notes (No F.B. # or page given) indicate a post on fence line, possible B.T.'s, a 1/2" iron 2" above surface, and an iron pipe with brass cap. References to F.B.'s #401, 526, and 762.

960: MCRC notes from F.B. #762 indicate a 1/2" iron pin 2" above ground surface on fence line. No accessories given.

993: An LCRC recorded by Gerald W. Carlson P.S. #24589, in L. 5, RC Pg. 404, indicates a found DNR 4" brass capped monument, 1.3' high (1940), and stamped to identify the corner in Cedar Swamp 900' North of Co. Rd. 492. Referenced by D.H. Nails and face blazes in:

0" Spruce	S60W,	16.32'	14" W. Birch	N55W,	22.25'
7" Cedar	N03W,	43.11'	8" Elm	S27E,	24.16'