

# SURVEY & REMONUMENTATION

JOB NUMBER: 94030

SHEET NO.: 1-434

For corners in

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

APR 28 1995

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

1994 DEC 28 PM 5:54

*Patricia L. Manley*  
REGISTER OF DEEDS

<u>MARQUETTE</u> (County)	<b>COMMISSION</b>	Located In:	Corner Code =#	
1. Public Land Survey	T <u>48N</u> R <u>25W</u>		D-13	
	T _____ R _____		_____	
	T _____ R _____		_____	
	T _____ R _____		_____	
2. Property Controlling in Section	S _____ T _____ R _____		_____	
	S _____ T _____ R _____		_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____	
	S _____ T _____ R _____		_____	
4. Lot No. _____, Recorded Plat _____				
5. Private Claims _____				

LIBER **1** PAGE **109**  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Wednesday, November 30, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

D-13: South Quarter Corner Section 32, T48N-R25W, 1844: William A. Burt's original survey notes describe the corner monument as a wood post referenced by: 8" Fir N45E, 34 l 15" Sugar N18W, 39 l	1988: G. Carlson set a 5/8" x 18" re-bar w/LLs cap equi-distant and on-line between the SE and SW Section Corners. Referenced by: 7" Y. Birch N80E, 26.60' 16" Y. Birch N21W, 38.69' 10" Maple S23W, 22.51' 10" Maple N87W, 35.31' This corner is not recorded.
--	---

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1994 - Found and accepted iron as placed by G. Carlson in 1988.  
 Distance West is 2654.51' and distance East is 2594.65'. GLO call to stream 732' East of corner checks within 12'.

**RATIFIED BY PEER GROUP  
P.A. 345 OF 1990**  
*Henry J. Busome*  
DATE Oct. 3, 1994

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1994 - Replaced 3/4" iron and cap #24589 with a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:  
 17" Yellow Birch N33W 38.68 ft. Carlson NBT  
 12" Maple S89W 35.28 ft. Carlson NBT  
 10" Yellow Birch N79E 26.57 ft. Carlson NBT  
 12" Maple S21W 22.53 ft. Carlson NBT  
 Steel sign post West 1.0 ft.  
 Monument is 0.40' above ground.  
 Bk. 5, Pg. 65



Signed by *Gerald W. Carlson* Date 12-22-94  
 Surveyor's Michigan License No. 24589