

1993

COMMISSION

JOB NUMBER: 93300

SHEET NO. : 1-330

For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Form with fields for County (MARQUETTE), Located In, Corner Code #, and numbered sections 1-5 for Public Land Survey, Property Controlling, etc.

RECEIVED FOR RECORD
MARQUETTE COUNTY MICHIGAN
1993 DEC 22 PM 4:12
Liber 1 R.C. Page 53
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Tuesday, December 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

A. Description of original monument and accessories and/or subsequent restoration:

E-1: Section Corner common to Sections 4 and 5. 1845: 1988 - G. Carlson set a 5/8 x 18" rerod with RLS cap #24589
William A. Burt's original survey notes describe the corner 73.92 ft. West of the SE corner of Section 32, T49N-R25W
monument as a wood post referenced by:
7" Y.Pine S28E, 19 1
6" Spruce S54W, 39 1
14" Red Pine S86E 8.60 ft.
10" Oak S05W 22.93 ft.
8" Red Pine S56W 19.33 ft.
12" Red Pine N02E 29.10 ft.
LS RC, Pg. 156

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found 5/8 iron with RLS cap #24589. Replaced with Marquette County Survey Monument.
Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Replaced 5/8 iron with RLS cap #24589 with a 2 1/8" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
13" Red Pine N02E 29.30 ft. Carlson NBT
17" Red Pine N83E 8.68 ft. Carlson NBT
12" Oak S03W 22.89 ft. Carlson NBT
11" Red Pine S59W 19.25 ft. Carlson NBT
Monument is 0.5 ft. above ground.
Bk. 3, pg. 86



Signed by Gerald W. Carlson
Surveyor's Michigan License No. 24589

Date 12-22-93