

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY  
 RECEIVED FOR RECORD  
 1995 DEC 27 AM 7:47  
 REGISTER OF DEEDS

For corners in

APR 01 1996

MARQUETTE (County)	Located In:	Corner Code ##
1. Public Land Survey	COMMISSION 48N 25W	E-5
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

LIBER 1 PAGE 273  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

GERALD W. CARLSON, in a field survey on Wednesday, October 18, 1995

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

- E-5: Section Corner common to Sections 8, 9, 16, and 17. 1932: The corner is indicated in MCRC F.B. 526, Pg. 36. No accessories given.
- 1846: William Ives' original survey notes describe the corner monument as a wood post referenced by:  
16" Y. Birch S70E, 14 l  
14" Sugar N73W, 28 l
- 1895: G.P. Cummings, County Surveyor, in Record of Surveys Pg. 129, indicates the corner as an iron pipe 2648' East of the South 1/4 Corner of Section 8. No accessories given.
- 1920: Corner shown on the Plat of Trowbridge Park Subdivision No. 8, recorded by Charles Cummings in L.4, Plats Pg. 26. sories given. (See Reverse Side)
- 1932: The corner is indicated in MCRC F.B. 526, Pg. 36. No accessories given.
- No Date: The corner is indicated on an Upper Peninsula Power Company Easement Map recorded in L. 61, MR Pg. 532.
- 1962: The corner is indicated on an Upper Peninsula Power Company Easement Map recorded in L. 63, MR Pg. 554.
- 1973: A Certificate of Survey recorded by William R. Donnan in L. 301, Pg. 262, indicates the corner as N00-20-10E, 2669.08' from the East 1/4 Corner of Section 17. No accessories given. (See Reverse Side)

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found and accepted a 2" Iron Pin just below surface of old roadway as referenced in Part "A" above. Distance North is 2662.01', Distance East is 2616.96', and Distance West is 2628.21'.

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990  
*Larry J. Russom*  
DATE Oct. 16, 1995

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1995: Replaced a found 2" Solid Iron Pin with a 2 3/8" O.D. Aluminum Pipe capped with a 3 1/4" diameter Aluminum Tablet Marquette County Survey Monument stamped to identify the corner. Existing references:
- 6" Oak (Existing d.h. nail w/washer) S01W, 36.09' Carlson NBT
- 6" Oak (New d.h. nail- old overgrown) S65W, 69.88' Carlson NBT
- 8" W. Birch (Existing d.h. nail w/washer) N17E, 27.88' Carlson NBT
- 8" Wood Post (Existing d.h. nail w/washer) S37E, 34.43' Carlson Accessory
- Set Green Steel Post w/ Yellow Survey Marker Sign N43W, 11.22'

Note: Monument is 0.1' below ground. Bearing Trees were repainted, butt blazes added, and B.T. Tags affixed.  
Bk. 11, Pg. 19.

ed by Gerald W. Carlson Date 11-13-95  
24589  
yor's Michigan License No. \_\_\_\_\_



