

MAY 22 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1996 DEC -4 AM 10:12

Patricia L. Monkey REGISTER OF DEEDS

Form with fields: For corners in MARQUETTE (County), Located In: T 48N R 25W, Corner Code # E-8, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims

LIBER 1 PAGE 336 Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on JUNE 27TH, 19 96, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: E-8: Quarter Corner common to Sections 20 and 21.

1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by: 14" Hemlock N20E, 25 L 8" Hemlock S20W, 23 L

1888: George Cummings, in Record of Surveys Pg. 151, indicates the corner as being 1316.0' South of the E.N.E. 1/16 Corner of Section 20, and 2632.0' South of the N.E. Corner of Section 20.

1904: Charles Cummings, in Record of Surveys Pg. 151, indicates the corner as being 2632.0' South of the N.E. Corner of Section 20.

1993: A Lot Survey Map by Gerald W. Carlson P.S. #24589 indicates the corner as a set 5/8" X 30" Iron with cap 20' North of C/L of railroad. Referenced by:

1" Oak N46E, 41.33' 7" W. Pine N73E, 53.43' 6" W. Birch N08W, 22.70' 6" Oak N45W, 53.06'

No Liber or page given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8: 1996: Searched and found no evidence of original B.T.'s. Found and accepted a 5/8" X 30" Iron with Cap. Distances to found references check reasonably well with those recorded by G. Carlson in 1993. Distance North is 2631.94' and Distance South is 2625.46'. This corner was set in 1983 at the intersection of a line from the West Quarter Corner through the Center Quarter Corner extended East (both State of Michigan survey monuments) and the straight line between the Northeast and Southeast Section Corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8: 1996: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is flush with ground. Added new d.h. nails above old ones on found references:

10" W. Pine N75E, 53.33' (Carlson NBT) 6" W. Birch N04W, 22.67' (Carlson NBT) 1" Oak N43W, 53.08' (Carlson NBT) 6" Oak N48E, 41.30' (Carlson NBT)

Set Green Steel Sign Post w/ Yellow Survey Marker Sign N18E, 1.95' Note: Bearing trees have painted face blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Grid table with columns A-M and rows 1-13. Cell (8,20) contains a black dot.

RATIFIED BY PEER GROUP P.A. 345 OF 1990 Larry J. Bussme DATE 11/11/96



Signed by Gerald W. Carlson Date 12-2-96 Surveyor's Michigan License No. 24589