

1998

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1998 DEC 29 PM 3: 22

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MARQUETTE (County)

Located In: Corner Code #

- 1. Public Land Survey T 48N R 25W E-12
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Patricia L. Manley REGISTER OF DEEDS

LIBER R 2 PAGE 113

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, GERALD W. CARLSON, in a field survey on DECEMBER 10th, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. Cell 12,33 contains a black dot.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: E-12: Quarter Corner common to Sections 32 and 33.

1845: William Ives' original subdivision survey notes describe the corner monument as a wood post referenced by: 8" Maple S44W, 21 L 22" Hemlock N10E, 20 L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12: 1998: No original corner evidence found. The corner was set equidistant and on line between the N.E. and S.E. corners of Section 32. Distances North is 2669.08' and South is 2669.06'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12: 1998: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.30' above ground. Established references:

- 8" Balsam S26E, 75.00' 9" Hemlock S33W, 78.95'
7" Maple N58W, 25.84' 6" Maple N16W, 12.81'

Green Steel Sign Post w/ Yellow Survey Marker Sign, N44W, 2.0'.

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

Bk. 13, Pg. 157-158

RATIFIED BY PEER GROUP P.A. 345 OF 1990

Signature of Harry J. Busone DATE 11/30/98



Signed by Gerald W. Carlson

Date 12-28-98

Surveyor's Michigan License No. 24589