

1893

COMMISSION

JOB NUMBER: 93300
SHEET NO. : 1-329
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1993 DEC 22 PM 4: 12
REGISTER OF DEEDS

<u>MARQUETTE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>25W</u>	<u>F-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Re: Liber 1 R.C. Page 4
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Tuesday, December 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1: North Quarter Corner Section 4. Not part of original 1988 - G. Carlson set a 5/8" x 18" rerod RLS cap #24589. 73.92 ft. West of the South 1/4 corner of Section 33, T49N-R25W online between the South 1/4 corner of Section 33, and the SW corner of Section 33, in accordance with the original government survey plat dimension. Iron is drilled and grouted in rock. Referenced by:
12" White Pine S05E 10.05 ft. 10" Jack Pine S45W 16.95 ft.
10" Red Pine N31E 13.67 ft. 8" Red Pine N40W 10.54 ft.
L5 RC, Pg. 157.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Found a 5/8 rebar as set by G. Carlson 1988. Set a 3 1/4" diameter aluminum tablet Marquette County Survey Monument on top of the grouted in rerod. Peer group ratification 12-6-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - 3 1/4" diameter aluminum tablet Marquette County Survey Monument on top of the grouted in 5/8" diameter rebar stamped to identify the corner referenced by nails in:
8" Red Pine N42W 10.51 ft. Carlson BT
11" Red Pine N31E 13.67 ft. Carlson BT
8" Red Pine N82E 9.36 ft. Carlson BT
14" White Pine S09E 10.01 ft. Carlson BT
0.25 ft. above ground.
Bk. 3, pg. 82



Signed by Gerald W. Carlson Date 12-22-93

Surveyor's Michigan License No. 24589