

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

MARQUETTE COUNTY  
 RECEIVED FOR RECORD  
 1995 DEC 27 AM 7:49  
 REGISTERED OF DEEDS  
 REGISTERED OF DEEDS

For corners in MARQUETTE (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

	48N	25W	G-10
1. Public Land Survey	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Section	S _____	T _____	R _____
	S _____	T _____	R _____

LIBER 1 PAGE 288  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

GERALD W. CARLSON Thursday, October 26 95

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G-10: Quarter Corner common to Sections 27 and 28. 1846:

William Ives' original survey notes describe the corner monument as a wood post referenced by:

- 3" Ironwood S10E, 15 l
- 14" Hemlock N24W, 25 l

1916: Charles Cummings, in Record of Surveys Pg. 165, indicates the corner as being 2672' South of the N.W. Corner of Section 27. No accessories given.

No date: The corner is indicated on an easement map for Northern Natural Gas company recorded in L. 72, MR Pg. 587.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1995: Found and accepted a 5/8" X 18" iron with RLS cap #27464 leaning in rocks, 1.3' high, and loose enough to pull out. Also found 4 existing face blazed trees. Distance North is 2669.24', Distance South is 2669.81', and Distance East is 5298.55'.

RATIFIED BY PEER GROUP  
P.A. 345 OF 1990

*Larry J. Boosma*  
DATE Oct 23, 1995

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1995: Replaced found 5/8" Iron with a 3/4" X 6" Iron, grouted in rock, and capped with a 3" diameter Aluminum Tablet Marquette County Survey Monument, 0.15' above rock, and stamped to identify the corner. Referenced by:

- 16" Maple S21W, 46.23'
- 14" Hemlock N78W, 42.00'
- 15" Maple N05W, 43.57'
- 10" Maple S88E, 24.92' (Placed Survey Marker Sign on Tree)

Note: We found trees with painted face blazes. We added double-headed nails, butt blazes, paint, and stamped B.T. Tags to these trees.

Bk. 11, Pg. 49.

Signed by Gerald W. Carlson

Date 11-13-95

Surveyor's Michigan License No. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JUN 28, 1971  
REVISED MARCH 1975  
REVISED JAN, 1983

