

JOB NUMBER: 95053
SHEET NO. : 1-614

APR 01 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1995 DEC 27 AM 7:49
REGISTER OF DEEDS
Dorothy M. Mankley

For corners in _____ Located In: _____ Corner Code # _____

_____ MARQUETTE (County)

1. Public Land Survey	T <u>48N</u>	R <u>25W</u>	G-11
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Section	S _____	T _____	R _____
	S _____	T _____	R _____

Register of Deeds Stamp & File Number
1 PAGE 289

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, GERALD W. CARLSON, in a field survey on Wednesday, October 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-11: Section Corner common to Sections 27, 28, 33, and 34.
1846: William Ives' original survey notes describe the corner monument as a wood post referenced by:
18" Sugar S31E, 36 l
8" Fir N57W, 24 l
No Date: The corner is indicated on an easement map for Northern Natural Gas Company recorded in L. 72, MR Pg. 587.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found and accepted a 5/8" iron with RLS cap #27464, 0.3' above ground, 48.5' East of centerline woods road and 1.8' North of fence post. Distance North is 2669.81', Distance South is 2613.51', and Distance East is 2654.53'. This corner was set by extending the line from the S.E. Corner Section 27 to the South 1/4 Corner Section 27 Westerly at a single-proportioned distance from the South 1/4 Corner Section 27 to the S.W. Corner Section 28. The distance from this corner to the N.W. Corner Section 27 checked within 5.12' of Cummings. The single-proportioned distance West is 8.02' longer than GLO in 1.5 miles.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990
Larry J. Wadsworth
DATE Oct 23, 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Replaced found 5/8" Iron and RLS Cap #27464 with a 2 3/8" O.D. Aluminum Pipe capped with a 3 1/4" Aluminum Tablet Marquette County Survey Monument, 0.3' above ground, and stamped to identify the corner. Found existing references, and replaced overgrown nails and washers #24589 with new Double Headed Nails in:
6" Y. Birch S49W, 16.10'
12" Poplar N86W, 31.88'
13" Hemlock N15E, 50.50'
7" Hemlock N57E, 35.21'
Set Green Steel Fence Post w/Yellow Survey Marker Sign South, 1.7'
Note: Repainted existing blazes, added butt blazes, and affixed stamped B.T. Tags to bearing trees.
Bk. 11, Pg. 41.

Signed by Gerald W. Carlson Date 11-13-95
Surveyor's Michigan License No. 24589

