

JOB NUMBER: 95053
SHEET NO. : 1-616

APR 11 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Located In:	Corner Code #
MARQUETTE (County)	G-12
1. Public Land Survey	T ^{48N} R ^{25W}
	T _____ R _____
	T _____ R _____
	T _____ R _____
2. Property Controlling in Section	S _____ T _____ R _____
	S _____ T _____ R _____
3. Miscellaneous Property in Section	S _____ T _____ R _____
	S _____ T _____ R _____

REGISTER OF DEEDS

MARQUETTE COUNTY
RECEIVED FOR RECORD
1995 DEC 27 AM 7:49

LIBER 1 PAGE 292
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, GERALD W. CARLSON, in a field survey on Friday, October 27, 19⁹⁵, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-12: Quarter Corner common to Sections 33 and 34. 1846:
William Ives' original survey notes describe the corner monument as a wood post on side hill descending north referenced by:
5" Sugar S60E, 16 l
20" Hemlock N15W, 08 l
No Date: MCRC notes from F.B. #654 indicate the corner as a 1/2" circular iron pin. No accessories given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995: Found and accepted a 1/2" iron with RLS Cap #25849 on South slope of hill in rocks, 0.4' above ground. Distance North is 2613.51', Distance South is 2631.01', and Distance East is 5235.65'. This corner was set by R. Jamros, P.S. No. 25849 while surveying for Benson Forests. The corner was set on line between the S.W. and N.W. Corners of Section 34 and the proportioned distance between the GLO Calls for C/L Stream and Summit of Ridge. The GLO Distance between calls was 2471.04' and measured was 2475.19', a difference of 4.15'.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussini
DATE Oct 33, 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1995: Replaced found 1/2" Capped Iron with a 2 3/8" Aluminum Pipe capped with an Aluminum Tablet Marquette County Survey Monument, 0.7' above rocky ground, and stamped to identify the corner. Corner falls on South Slope of Hill. Painted exposed shaft of monument. Found existing references with painted face, butt, and nail blazes, and PK Nails with Washers "B.F. 25849". All trees except Oak are scribed "1/4 S BT". Repainted blazes on references:
3" Oak N85W, 42.62'
9" W. Birch (Cluster of 5) N55W, 67.92'
5" Poplar N28E, 21.43'
5" Spruce Due East, 51.60'
Set Green Steel Fence Post w/Yellow Survey Marker Sign S33W, 2.67'
Bk.11, Pg. 51.



Signed by Gerald W. Carlson
Surveyor's Michigan License No. 24589

Date 11-13-95