

SURVEY & REMONUMENTATION

JOB NUMBER: 94030

SHEET NO. : 1-442 **APR 28 1995**

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 29 AM 10:55

For corners in MARQUETTE **COMMISSION**

	Located In:		Corner Code ##
	48N	25W	
1. Public Land Survey	T _____	R _____	H-13
	T _____	R _____	
	T _____	R _____	
	T _____	R _____	
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Patricia A. Manley
REGISTER OF DEEDS

LIBER **1** PAGE **115**
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Wednesday, December 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
H-13: South Quarter Corner Section 34, T48N-R25W. 1844:

William A. Burt's original survey notes describe the corner monument as an 8" Hemlock referenced by:
6" Hemlock N33E, 10 l

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: No original evidence found. Found a Benson Forests iron and cap that was set equidistant between the found SW and SE Corners of Section 34 and on line from the SE Section Corner through the found Hemlock line tree stump 11.6 chains East of the 1/4 Corner. This GLO call checked less than 1' from the GLO distance. The distance West is 2622.08' and the distance East is 2621.52'. Robert Jamros, P.S. of Benson Forests gave his explanation of the corner at the Marquette County Peer Group meeting. The North 1/4 Corner Section 3, T47N-R25W, is West 3.58'.

**RATIFIED BY PEER GROUP
P.A. 345 OF 1990**

Larry J. Bussard
DATE Oct. 3, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Replaced 1/2" iron and cap #25849 with a 3/4" diameter rebar capped with a 3 1/4" diameter aluminum tablet
Marquette County Survey Monument stamped to identify the corner referenced by nails in:
11" Maple S40E 20.25 ft. Jamros NBT
8" Maple S63W 24.59 ft. Jamros NBT
13" Twin Maple N23W 33.44 ft. Jamros NBT
26" Hemlock N30E 34.10 ft. Jamros NBT
Steel sign post North 2.0 ft.
Monument is 0.20' above ground and is grouted in rock on North slope of hill.
Bk. 8, Pg. 85



Signed by Gerald W. Carlson
24589

Date 12-29-94

Surveyor's Michigan License No. _____