

SURVEY &
REMONUMENTATION

JOB NUMBER: 94030
SHEET NO. : 1-462

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1994 DEC 28 PM 5:55

For corners in

COMMISSION

Patricia L. Mackay
REGISTER OF DEEDS

MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>25W</u>	I-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER 1 PAGE 133
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GERALD W. CARLSON, in a field survey on Tuesday, December 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-2: Quarter Corner common to Sections 2 and 3. 1845: 1327.4'.
William Ives' original survey notes describe the corner 1895: A survey by George P. Cummings indicates the East 1/4 monument as a wood post referenced by: Corner of Section 3 with a deflecting angle at the 1/4 Corner to the North of 1-15'. Distance South 2654.8', and Distance North of 330' to the Meander Corner on the shore of Lake Superior. (See reverse side after 1909 record).
6" Y. Pine S02W, 305 L On small lone ridge. No other tree convenient.
1892: The Plat of Island Beach Addition surveyed by George P. Cummings indicates the West 1/4 Corner of Section 2 with an angle on the East Side of the West Line of Section 2 at the 1/4 Corner of 181-13', and the Distance South listed as 330' North. No accessories given.
1909: The recorded plat of Presque Isle Addition surveyed by Charles Cummings indicates the 1/4 Corner and the Meander Corner North of there 330' North.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found and accepted the iron pipe as referenced in Part A above. The Distance South is 2653.64'.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990
Larry J. Busan
DATE Oct. 17, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Drove an 8.0' long 3/4" re-rod inside the found 1 3/4" iron pipe and capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:
6" Tamarack S45E 37.37 ft. Carlson NBT
4" Tamarack S30W 49.09 ft. Carlson NBT
9" Maple N02E 94.23 ft. Carlson NBT
13" Red Pine N38E 98.00 ft. Carlson NBT
Steel sign post S05E 1.00 ft.
Monument is 0.3' above ground and is in an open marshy area.
Bk. 5, Pg. 123 and Bk. 7, Pg. 1



Signed by Gerald W. Carlson Date 12-22-94
Surveyor's Michigan License No. 24589

Record No. 462:

Part "A" Continued:

1988: Gerald Carlson LLS No. 24589 found a 1 3/4" pipe in bog. Distance to SE Corner of Section 3 checked well to Cummings' survey. Set wood post along side iron pipe. Referenced by:

6" Tamarack	S45E,	37.37'
4" Tamarack	S30W,	49.11'
9" Maple	N02W,	94.23'
15" Red Pine	N32E,	97.97'

L. 5 R.C., Pg. 151

*Rte 6446
Geo Sem
300 Sem*