

**SURVEY &
REMONUMENTATION**

JOB NUMBER: 94030
SHEET NO. : 1-461

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD

1994 DEC 28 PM 5:55

For corners in
MARQUETTE

COMMISSION

		Located In:	Corner Code #
(County)		48N 25W	I-3
1. Public Land Survey	T	_____ R _____	_____
	T	_____ R _____	_____
	T	_____ R _____	_____
	T	_____ R _____	_____
2. Property Controlling in Section	S	_____ T _____ R _____	_____
	S	_____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S	_____ T _____ R _____	_____
	S	_____ T _____ R _____	_____

Patricia L. Morley
REGISTER OF DEEDS

LIBER **1** PAGE **132**
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

GERALD W. CARLSON Monday, November 21 94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
I-3: Section Corner common to Sections 2, 3, 10, and 11, 1975: A survey recorded in Liber 315, Pg. 235 of Gourdie, T48N-R25W. 1845: William Ives' original survey notes describe the corner monument as a wood post referenced by: 12" Red Pine S56W, 20.47' 6" Jack Pine N46E, 8.58' 10" Jack Pine N08W, 34.30' 1975: A survey recorded in Liber 315, Pg. 235 of Gourdie, Frasier, and Associates indicates a found 1 1/2" iron pipe referenced by: 12" Red Pine S56W, 20.47' 6" Jack Pine N46E, 8.58' 10" Jack Pine N08W, 34.30' 1892: Survey by George P. Cummings indicates a corner at the NE Corner of Section 10, the Distance West listed as 2618.2', No Date Given: LS&I Railroad Company map indicates the the Distance South is 2670' (listed as calculated), and the corner with a distance West of 1310.55'. interior angle at the NE Corner of Section 10 is 89-15'. (See reverse side).
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994: Found and accepted the iron pipe as referenced in Part A above. The Distance South is 2669.23' and the Distance North is 2653.64'.

RATIFIED BY PEER GROUP.
P.A. 345 OF 1990
Larry J. Busare
DATE Oct 17, 1994

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1994 - Replaced 2" diameter iron pipe with a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet
Marquette County Survey Monument stamped to identify the corner referenced by nails in:
14" Red Pine S57W 20.68 ft. Clark NBT
7" Jack Pine N48E 8.62 ft. Clark NBT
6" Jack Pine S50E 15.13 ft.
9" Jack Pine N09W 34.08 ft. Clark NBT
Steel sign post East 0.7 ft. (next to wood post)
Monument is 0.1' above ground and located in a pine stand South of power line.
Bk. 4, Pg. 148



Signed by *Gerald W. Carlson* Date 12-22-94
24589

Surveyor's Michigan License No. _____

Record No. 461:

*R# 6446
900
Rem*

Part "A" Continued:

No Date Given: The easement map of the Upper Peninsula Power Company recorded in Liber 90, Pg. 5 indicates the corner South of their transmission line.

No Date Given: The easement map by the Upper Peninsula Power Company recorded in Liber 93, Pg. 497 indicates a corner 70' South of their transmission line.

No Date Given: An easement map by the City of Marquette, Board of Light and Power indicates the NE Corner of Section 10 as an iron pin. Distance West is 1309.76'.

1979: Charles Clark RLS No. 25836 found a 2" iron pipe and post as noted in records of Cleveland Cliffs Iron Company and LS&I Railroad. Referenced by:

Nail and Tags in:	6" Jack Pine	N48E,	8.55'
	12" Norway Pine	S58W,	20.48'
	10" Jack Pine	N06W,	34.20'

L. 1 R.C., Pg. 318.