

SURVEY &  
REMONUMENTATION

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

JOB NUMBER: 94030  
SHEET NO. : 1-457

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 5:55

For corners in

COMMISSION

*Patricia R. Monley*  
REGISTER OF DEEDS

MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 25W	I-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER 1 PAGE 130  
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Tuesday, November 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-5: Section Corner common to Sections 10,11,14, and 15, T48N-R25W. 1845: William Ives' original survey notes describe the corner monument as a wood post referenced by: 10" Y. Pine S49W, 07 L; 10" Y. Pine N46E, 17 L; 1891: County survey by George P. Cummings indicates a Corner at the S.E. Corner of Section 10 with distances West of 2645.5' and North of 2655.8'. No corner accessories given.

No date: County survey of Section 11 indicates a iron pipe identified as the S.W. Corner of Section 11. Distances East of 2616.6' and North of 2655.8'. 1910: A county survey by Charles Cummings indicates a corner with distances West 2645.5' and South of 2658'. 1916: The N.W. Corner of Section 14 is shown on the recorded plat of Woodlawn Park Addition. Surveyed by P.T. Allen. No corner accessories given. (See reverse side).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Corner is accepted as referenced by G. Carlson in Part A above. The Distance South is 2659.50' and the Distance North is 2654.09'. The corner position falls in the crack between the cover and rim of a manhole in the centerline of the intersection of Wright St. and Sugar Loaf Ave. (Co. Rd. 550). A Reference Monument was set S49°39'19"W, 70.00' from the corner position on line from the corner to the Northeast corner of the Olympic Training Center Building sighting the corner of the 7th brick up from the ground. (See sketch on back)

ATIFIED BY PEER GROUP  
P.A. 345 OF 1990  
*Larry J. Buswell*  
DATE Oct. 17, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Set a 2 1/2" diameter aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument (Reference Monument) stamped to identify the corner referenced by nails in:  
16" Red Pine S06E 53.39 ft. 16" Red Pine S40W 33.37 ft.  
12" Red Pine S26W 43.36 ft. 16" Red Pine S65W 71.69 ft.

Monument is a Reference monument to the true corner location and is buried 0.40' below ground in lawn. Only nails were set in trees no blazing or painting was done. N49°39'19"E, 70.00' from the R.M. to Section Corner. R.M. and Northeast corner Olympic Training Center building (7th brick up from ground) are on line to corner.  
(see sketch on back)

Bk. 4, Pgs. 152 - 154; Bk. 5, Pg. 45

Signed by Gerald W. Carlson Date 12-28-94  
Surveyor's Michigan License No. 24589



